

The Mining And Metallurgical Journal

VOL. XIX, No. 10

LOS ANGELES, CAL.,

August 15, 1898,

SAN FRANCISCO, CAL.

Price 15 Cents

Jessop's STEEL

The Best
...FOR

Mining Drills,
Tools, Etc.

I. WILLARD BEAM,

29 Main Street
SAN FRANCISCO, CAL.


THE EDWARD P. ALLIS COMPANY
— MANUFACTURERS OF —

Mining, Milling and Smelting Machinery

Crushers, Concentrators, Pumps, Compressors, Hoists, Boilers,
Reliance Crushing Rolls, Reynolds Corlies Engines, &c.

Send for Catalogue.

Milwaukee, Wis.



A Modern Battery!

Shoes and Dies Unequaled.

First-class Workmanship

GENERAL MINING MACHINERY

Crushers, Rolls, Steam Stamps,
Vanners, Jigs, Furnaces, Hoists.

Gates Iron Works, 650 Elston Ave.

Department 2

CHICAGO

— THE —
ROESSLER & HASSLACHER Chemical Co.

100 William St., New York

CYANIDE

Peroxide of Sodium

Hyposulphite of Soda

Chloride of Lime

Sulphide of Iron



Trade Mark

And Other Chemicals for Mining Purposes.

Joseph Dixon Crucible Co.

MINERS, IMPORTERS AND MANUFACTURERS

GRAPHITE & PLUMBAGO

JERSEY CITY, N. J.

RETORTS, CRUCIBLES, GRAPHITE LUBRICANTS, BELT DRESSING,
GRAPHITE PAINTS, LEAD PENCILS, AND GRAPHITE
PRODUCTS OF ALL KINDS.

Send for Production Catalogue.

Graphite Makes the Best Lubricant
and Best Paint.

ADAMANTINE SHOES & DIES

AND

CHROME CAST STEEL

Cams, Tappets, Bosses, Roll
Shells and Crusher Plates.

These castings are extensively used in all the Mining
States and Territories of North and South America. Guarantees
to prove better and cheaper than any others. Orders
collected subject to above conditions. When ordering send
sketch with exact dimensions. Send for Illustrated Circular.

CHROME STEEL WORKS,

Kent Ave. & Keap St., - BROOKLYN, N. Y.



Stamp Shoes

Stamp Dies




Stamp Cam

PARKE & LACY COMPANY

21 and 23 FREMONT STREET, SAN FRANCISCO, CAL.

LICENSEE FOR THE MANUFACTURE AND SALE OF

The Huntington Centrifugal Roller Quartz Mill



THE HUNTINGTON MILL is so well and
favorably known among mining men throughout
the world that any description of it would seem
superfluous. They are in use in the United
States, Canada, Mexico, Central and South
America, Australia, China, Japan, and South
Africa. In fact, wherever mines exist, and have
given the best satisfaction of all quartz crushing
mills.

The construction of this mill has lately been much improved and we claim it to be the
CHEAPEST, MOST EFFICIENT, SIMPLEST, AND MOST DUR-
ABLE MILL UPON THE MARKET.

← CATALOGUE UPON APPLICATION →

The Pelton Water Wheel

Affords the Most Economical and Reliable Power for Mining,
Electric and all other purposes.

9000 WHEELS NOW RUNNING

PELTON WATER WHEEL CO., 121 Main St., San Francisco, Cal.

Mexican, American and Foreign Patents,
TRADEMARKS, ETC.


Reports on Mining and Other Properties.
Proprietors of *Weekly Anglo-American*, a first-class Advertising Medium.
Established 9 Years.

C. H. M. y Agramonte,

P. O. Box 388. Cable Address, "Agra" CITY OF MEXICO, MEXICO

Refractory Ores

Successfully treated by the
PORTER ELECTRICAL PROCESS



The Porter Gold and Silver
Extraction Company

505 BULLARD BLOCK.

LOS ANGELES, CAL.

OTTO HECKELMANN

FERDINAND MCCANN

ASSAYERS AND CHEMISTS

Heckelmann & McCann + + Bullion Dealers

Cash paid for all kinds of Gold, Silver and Ores. All assays
and Chemical Analysis at Mexican Silver Rates, 50
per cent. Less than American Price.

PUNTE DE SAN FRANCISCO, No. 6

CITY OF MEXICO


California Vigorit Powder Co.

Manufacturers of

Dynamite High Explosives and "Vigorit Low" Blasting Powder

OFFICE: 208 California Street,
San Francisco, Cal.WORKS: Point Isabel,
Contra Costa Co. Cal.

"Union" Hoist



Union Gas or Oil Engine and Hoist Combined, on strong, iron base.

No Fire No Steam No Boiler No Danger

TEN YEARS' EXPERIENCE. TWO THOUSAND ENGINES IN USE.

Started instantly. Compact, strong, simple, efficient, economical. Perfectly governed, so that oil is used only in proportion to the work done. No expense when idle.

**Particularly Adapted to Mining in Localities Where
Fuel and Water are Expensive.**

Built in the following sizes:—1 H.P., 4 H.P., 6 H.P., 8 H.P., 10 H.P., 15 H.P., 20 H.P., 30 H.P., 40 H.P.

Send for Catalogue and state what H. P. required.

Union Gas Engine Co.,

301 Howard Street. - San Francisco, Cal.

YUKON BOATS AND SLEDS

Stern Wheel Boats, 25 ft. to 200 ft. in length. Light draught. Shipped—knocked down—and set up ready to run. Send for circulars and prices.

SAN FRANCISCO LAUNCH CO. Cor. of North Point and Stockton Sts. San Francisco, Cal.

The only Genuine ALBANY GREASE has this TRADE MARK on every package. Look out for Yellow Label.


ALBANY GREASE
 Lubricates Everything
 Especially Adapted to Mining and Milling Machinery.
 MADE ONLY BY
ADAM COOK'S SONS,
 313 WEST ST., NEW YORK.
 BRANCHES:
TATUM & BOWEN,
 34 Fremont Street, San Francisco, Cal.
 42-49 First St., Portland, Oregon.
 55 So. Canal Street, Chicago, Illinois.

FRANCIS SMITH & CO.,
 MANUFACTURERS OF


MINING PIPES ALL SIZES

Hydraulic, Irrigation and Power Plants, Well Pipe, Etc., all Sizes.

Iron cut, punched and formed, or making pipe on ground where required. All kinds of Tools supplied for making Pipe. Estimates given when required. Are prepared for coating all sizes of Pipes with Asphaltum.


130 Beale Street

San Francisco, Cal.

Eclipse Sectional Rainbow Gasket

 3/4 in. for pipe unions
 1 1/2 in. for hand-holes
 3/4 in. for man-holes
 3/4 in. for extra large man-holes

 FOR
 UNION
 STAND HOLES
 AND
 MAN HOLES

**Peerless Rubber
M'g Co.**
 16 Warren St.
 New York City
16-24 Woodward Avenue, Detroit, Mich.
Dunham, Carrigan & Hayden Co., San Francisco, Cal.

Fac-simile of a 6-in section of Eclipse Gasket showing name and Trade-mark imbedded

T. & B.

STEEL MINING PIPE

— FOR —

HYDRAULIC, PLACER AND QUARTZ MINING

Riveted up complete or Cut and Punched to be Riveted at the mine.

Well Pipe, Galvanized Air Pipe, Wrought and Cast Iron Pipe. Iron Tanks of all kinds. Water Supply Material. General Sheet Iron Works.

Correspondence Invited

Send for prices

THOMSON & BOYLE CO.

306-318 Requesena St.,

Los Angeles, Cal.

WILLIAM H. EMANUEL,

REPRESENTING

 RAND DRILL COMPANY, Air Drills and Compressors
 THE EDW. P. ALLIS CO., General Mining, Milling and Smelting Machinery and Reynolds Corliss Engine
 TRENTON IRON CO., Wire Rope and Bleichert Tramways
 HENRY R. WORTHINGTON, General Service and Mining Pumps
 ROBIN'S BELT CONVEYOR

DENVER

COLORADO

RICHARD L. COLBURN,

 Stock and
 Mining Broker

Member of -- Salt Lake Stock and Mining Exchange SALT LAKE CITY, UTAH.

JUST PUBLISHED

SECOND EDITION, REVISED AND MUCH ENLARGED.

Gas, Gasoline and Oil Engines

BY GARDNER D. HIBOOK, M. E.

The only American book on the subject. 344 pages, 8vo, illustrated with 270 handsome engravings. Price \$2.50. Full of general information about the new and popular motive power, its economy and ease of management. Also chapters on Horseless Vehicles, Electric Lighting, Marine Propulsion, etc. Copies sent prepaid on receipt of the price. Our large book catalogue of 96 pages, covering every branch of practical science, sent free on request. Address

NORTON W. HENLEY & CO.

132 Nassau Street, New York

TRIPP METALLIC PACKING

FOR
PISTON RODS

Mining Trade Solidified

WM. B. MERRILL & CO.,
SOLE MANUFACTURERSOffice and Factory, 295 Congress Street
BOSTON, MASSACHUSETTS

PATENTS!

TOWNSEND BROTHERS
SOLICITORS
OF PATENTS

Patents on Inventions secured in all countries. Copyrights, Trade Marks and Labels.

Office, 9, Downey Block.
Telephone 347. Los Angeles, Cal.

WOODBURY CONCENTRATOR



No. 141 First St., - San Francisco

McDearmon & Co.

Asbestos Boiler & Steam Pipe Coverings
Asbestos Cement for Boilers, drums, Heaters, Etc. Special facilities for supplying the mining trade.

Pacific Coast Agent for E. W. John's Co's Asbestos Sectional Coverings.

422 Sacramento Street, - San Francisco, Cal.

MACHINERY

STAMP MILLS, Marine and Stationary ENGINES and BOILERS, Saw Mills and all kinds of new and second hand machinery.

Send for Catalogue
WASHINGTON MACHINERY DEPOT
TACOMA, WASHINGTON

J. W. Paxson Co.

FOUNDRY

Facings, Supplies, Equipments

COMPLETE OUTFITS

* Philadelphia, Pennsylvania

ALPHABETICAL INDEX TO ADVERTISERS

A		B		C		D		E		F		G		H		I		J		K		L		M		N		O		P		Q		R		S		T		U		V		W		X		Y		Z	
Abbott, W. O.	23	Baker & Co.	18	Caldwell Bros.	21	Dame, W. E.	18	Ellis, H. R.	27	Faith & Co.	27	Garratt & Co., W. T.	27	Hamlin & Morrison	27	Imperial Chemical Co.	22	Jackson Drill and Manufacturing Co., The	26	Keuffel & Esser Company	6	Lambert Holding Engine Co.	22	Machinery and Electrical Co.	29	National Iron Works	5	Oblandt & Co., N.	29	Pacific Mining Machinery Co.	21	Queen & Co.	24	Reed, John T.	30	Santa Fe Route	22	Taylor & Co., John	27	Union Gas Engine Co.	22	Van Der Nulien, A.	6	Wade & Wade	18	Yawger, I. C.	21				
Aetna Powder Co.	4	Baker & Co.	18	Cal Bellows Mfg Co.	24	Daniel, C. A.	28	Emmanuel, Wm. H.	27	Fay & Ragan Co., J. A.	28	Gates Iron Works	27	Hassell Iron Wks Co.	27	Incorporated Mines Paying Dividends	20	Jeffrey Manufacturing Co.	24	Kohlbusch, Sr. Herman	26	Leffel & Co., James	27	Masters, J. H.	17	National Pipe Bending Co.	26	Oblandt & Co., N.	29	Pacific Optical Company	18	Quick, John W.	29	Read, Edward R.	25	San Francisco Lumber Co.	2	Taylor Iron and Steel Co.	6	Union Hardware & Metal Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21				
Agramonte, C. H. M. Y.	20	Baker & Co.	18	California Perforating Screen Co.	25	Davis, I. P.	17	Kynon-Evans Manufacturing Co.	26	Perrari, Guido	28	Giant Powder Co., Con	28	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lexow, Theo.	21	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Selby Smelting & Lead Co.	23	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
Ainsworth, Wm.	24	Baker & Co.	18	California Wire Works	24	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
Albuquerque Foundry & Machine Works	24	Baker & Co.	18	Chapman Smelting Works Co.	24	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Selby Smelting & Lead Co.	23	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
Allis Co., Edward F.	1	Baker & Co.	18	Chester Steel Castings Co.	22	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
Altender & Sons, Theo.	4	Baker & Co.	18	Chicago & Aurora Smelting & Refining Co.	28	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Selby Smelting & Lead Co.	23	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
American Diamond Rock Drill Co.	4	Baker & Co.	18	Chicago School of Assaying	24	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
American Zinc Lead Co.	10	Baker & Co.	18	Chrome Steel Works	1	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
Aubury, L. R.	10	Baker & Co.	18	Coates, H. E. G.	1	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Colburn, Richard L.	2	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Selby Smelting & Lead Co.	23	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Colorado Iron Works	28	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Cook's Sons, Adam	2	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Selby Smelting & Lead Co.	23	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Colo. and Cal. Mineral Development Co.	2	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Compania Industrial Mexicana	2	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Conway & Co., P. J.	2	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Consolidated Pipe Co.	4	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						
		Baker & Co.	18	Con. Kansas City Smelting & Refining Co.	30	Davis, I. P.	17			Perrari, Guido	28	Globe Iron Works	22	Harrison & King Perforating Co.	24	Harper & Reynolds Co.	24	Jeffrey F. M.	2	Krogh Manufacturing Co.	19	Lidgerwood Manufacturing Co.	6	Merrill, William B. & Co.	2	New Haven Mfg Co.	25	Oblandt & Co., N.	29	Pacific Tank Co.	18	Reed, John T.	30	Simonds & Vainwright	30	Stewart, John	22	Union Gas Engine Co.	22	Van Nostrand Co., D.	18	Warren, A. A.	18	Zachary, J. C.	21						

Crude Platinum Purchased.

To Identify Crude Platinum when found, send 75c for Sample in glass, packed in a strong box. We purchase or refine anything containing Platinum.

BAKER & COMPANY,

NEW YORK OFFICE: 121 Liberty Street.

NEWARK, NEW JERSEY

John Wigmore and Sons Co.,

GENERAL MINING SUPPLIES

HEAVY HARDWARE IRON AND STEEL

AGENTS FOR

John A. Roebling's Sons Company's

WIRE CABLES

Giant Powder

117 to 123 S. Los Angeles St.,

LOS ANGELES, CALIFORNIA

DICKMAN & MACKENZIE
MINING ENGINEERS,
ASSAYERS AND CHEMISTS

1224 Rookery Bldg., Chicago Box 77, El Paso, Texas

Orders by mail or express promptly attended to. Mining properties examined.

F. M. JEFFERY,
MINING LAWYER

212 Wilcox Bldg., Los Angeles, Cal.


Five years in Cripple Creek, Colo.

WEBER

Gasoline Hoisting
Engine....

Money Savers

Costs to run ONE CENT per Horse
Power Per Hour. No Coal or Wood
and Very Little WATER REQUIRED



This Cut represents our 10, 15, 20, 30, 40
50, H. P. Geared Hoist

We also build Single and Double Drum Hoisting Engines, both Geared or Friction, and furnish Wire Rope, Ore Buckets, Cars, Shives, etc., making complete outfits. "Weber" Hoisters and Engines use Gasoline, Naptha, Distillate, etc., for fuel. They can be used Underground or on the dump. Altitude makes no difference in the operating of the "Weber."

Safe! Stiff! Strong!

Every Engine Sold on an Absolute Guarantee. In use for all purposes. Used by such concerns as Consolidated K. C. Smelting and Refining Co., Philadelphia Smelting Co., Guggenheim, etc. For prices and particulars write us, stating duty required, Horse Power, etc. Catalogues, "Stationery" and "Hoisting" on application.

Weber Gas and Gasoline Engine Co.

434 S. W. BOULEVARD,

KANSAS CITY, MISSOURI

CHAS. C. MOORE & CO.

ENGINEERS AND DEALERS IN

BABCOCK & WILCOX BOILERS, GREEN'S ECONOMIZERS,
McINTOSH & SEYMOUR ENGINES, WHEELER CONDENSERS,
HAMILTON CORLISS ENGINES, BARNARD-WHEELER COOLING TOWERS,
N. Y. SAFETY AUTOMATIC ENGINES, HOPKES LIVE STEAM PURIFIERS,
GOUBERT FEED WATER HEATERS, EDMISTON FEED WATER FILTERS,
STRATTON STEAM SEPARATORS, BUNDY STEAM TRAPS,
SNOW STEAM PUMPS, SPENCER DAMPER REGULATORS,
QUIMBY SCREW PUMPS, HYATT ROLLER BEARINGS.

Watch this Space for description of the above Machinery.

19 First Street, San Francisco, Cal.

Send for Catalogue and Full Information.

GOODYEAR'S RUBBER GOODS

Miners and Mining

CATHERING RUBBER, Crack Proof Boots, White Rubber Coats, Oil Clothing

BELTING, PACKING AND HOSE

573, 575, 579 Market Street,
SAN FRANCISCO, CAL.

73 and 75 First St.
PORTLAND, OREGON

Diamond - Pointed Core Drills

AMERICAN
DIAMOND ROCK DRILL CO.
170 Liberty St., New York.
P. O. Box 1412.

SETS OF ORES

Scientifically and Practically Arranged
Invaluable for reference in the work of the prospector, engineer or chemist. Illustrated Catalogue Free

Prices of Collections \$3.50 and Upwards

Specimens Purchased

Of Ores or Fine Crystallizations
Correspondence Solicited

DR. A. E. FOOTE, 1317 Arch Street
Philadelphia, Pa.
ESTABLISHED 1856

JENA Trade Mark
Normal Glass

SCHOTT & GEN.
JENA

BEST GLASS FOR Laboratory Use

CHEMICALS AND CHEMICAL APPARATUS

ASSAY BALANCES
Finest Ever Made

Specialties:—Analytical Portable Balances, Porcelainware, Platinum goods, Crucibles, Cupels, Scorifiers, Muffles, Furnaces, C. P. Adds, etc.

Everything Necessary for Assayers

Elmer & Amend,
3d Ave. Cor of 18th St. New York

Advertise in The Journal

J. HOWARD WILSON
Assayer and Chemist

A Specialty Made of Umpire Work.

306 Santa Fe Ave., Pueblo, Colo.

Just Published

Manual of Hydraulic Mining
FOR THE USE OF THE
PRACTICAL MINER
By T. P. VAN WAGENEN

NEW AND REVISED EDITION
16mo, cloth, \$1.00.

D. VAN NOSTRAND CO.
PUBLISHERS
23 Murray and 27 Warren Sts., New York
Copies sent by mail on receipt of Price.

CONSOLIDATED PIPE COMPANY,
IRON AND STEEL WATER PIPE A SPECIALTY

873-889 STEPHENSON AVENUE, LOS ANGELES, CAL.

A. C. HARPER, Proprietor.
Telephone Main 420 Post Office Box 867

THE COLORADO and CALIFORNIA Mineral Developing Co.

433-4-5 STIMSON BLOCK, LOS ANGELES, CAL.

Prospecting, Developing of Mines, Mine Operators, Locating, Buying and Selling of Mines a Specialty, Financial Agents for Eastern Capitalists.

GAIL BORDEN, President
J. A. COMER, Vice-President
J. K. HAWK, Secretary

CAPITAL STOCK, \$200,000
Correspondence Solicited

ELECTRICAL FUZES

BLASTING MACHINES
LEADING WIRE
CONNECTING WIRE

THE AETNA POWDER CO.
188 MADISON STREET
CHICAGO - ILL.

Send for our illustrated pamphlet


A NEW MORTAR
That is a crusher and pulverizer combined.



Weight 110 lbs.; Diameter 10½ in.; Height 8½ in.
Fills a long-felt want. Send for descriptive circular. Crusher Pulverizer No. 1, \$45.00.
J. E. Surman & Co., 74 Cortlandt St., New York.

Lidgerwood Hoisting Engines

Built to gauge on the Duplicate Part System. Quick Delivery Assured.



HENSHAW, BULKLEY & CO., Agents, San Francisco.

New York

Mine Hoists, CABLEWAYS


Conveying Devices, for Mining, Quarrying, Logging, Dam Construction, &c.

Electric Hoists and Appliances
Lidgerwood Mfg. Co.

J. A. FAY & EGAN CO

CINCINNATI, OHIO

Wood Working Machinery



— FOR —

Box Factories, Planing Mills, Sash, Door & Blind Factories
Carriage, Wagon and Agricultural Shops.

HENSHAW, BULKLEY & CO., Agents, San Francisco, Cal

THE NATIONAL IRON WORKS



Riveted Boilers, Tanks, and Sheet Steel or Iron Work of every description.


MANUFACTURER OF THE

National Steel Ore Car

Repairing of All kinds Promptly Attended to.
PORTLAND, OREGON

The F. M. Davis Iron Works Co.

Office and Works 723 to 743
LARIMER STREET,
Corner 8th Street, DENVER, COL.



Our Stamp Mills from 500 lbs. to 1,000 lbs. Stamps are strictly up to date. Furnished with Steel or Semi-Steel wearing parts, heavy mortars of late improved design, with or without steel linings, as desired, and the Davis Patent Self-Tightening Cam of High-Grade Open-Hearth steel, and, High-Grade Forged-Steel Cam Shafts and Stems.

They are designed with great care by engineers familiar with the best previous practice and knowing just what is wanted to render satisfactory service.

Send for Catalogue and Prices.

OUR New Book

ESSAYS UPON

Boiler Incrustation and Corrosion.
Boiler Explosions, The History of
Natural Water Contamination.

BY GEO. W. LORD, is now ready

We will send this interesting little book free of cost to

EVERY SUPERINTENDENT OR ENGINEER

Who will state his occupation. By whom employed. Total Boiler capacity. What Scale preventive he is using. The cost of the article. And how long the supply will last. Address

Geo. W. Lord, Philadelphia Pa.

J. B. TOMLINSON, M. E.
Prescott, Arizona,

MINING PROPERTIES EXAMINED, AND
PRAISED AND REPORTED UPON

Supervision taken of the development of prospects and the operation of mines.

S. S. MACHINERY CO.

Buy, Sell and Trade in All Kinds of SECOND-HAND
Mining and Wood Working Machinery.

CORRESPONDENCE SOLICITED.

DENVER, COLORADO

OFFICE: 1529 Lawrence
WORKS: Sixth and Market

TELEPHONE: Office, 130
Works, 1334

THE JOHANNESBURG SAMPLING WORKS


Purchasers of Gold, Silver, Copper and Lead Ores and Concentrates

Cash Returns Made Within Twenty-four hours after receipt of Ore.

CHAS. R. WORES, MANAGER.

Johannesburg, Cal.

LONERGAN & CALKINS' Combined Melting and Muffle Furnace.



"This cut shows the Oxidizing Bonnet by which a continuous flow of fresh air controlled by a damper is passed through the muffle."

LONERGAN & CALKINS,

Gold and Silver Refiners,
Assayers and Bullion Buyers.

127 West First Street,

LOS ANGELES, CAL.

THE TRUAX PATENT IMPROVED

AUTOMATIC ORE CARS

Manufactured by

CHAS. B. BOOTHE & Co.

126-128
SOUTH LOS ANGELES ST.
LOS ANGELES, CAL.



Pat. Jan. 2, 1892. Pat. Aug. 27, 1895.

Send for our Catalogue and Prices

Bullock's Diamond Prospecting Core Drills

These are the only Machines which will give absolutely accurate records of borings. Fifteen styles and sizes. Operated by hand, horse, steam, air or electricity.

Monarch Rock Drills

Any style of mounting. Simple, compact, economical. Operated by air or steam
Hoisting and Haulage Machinery to fill any requirements.

M. C. BULLOCK MFC. CO.,

1178 West Lake Street,

CHICAGO, ILLINOIS


* SCHOOL OF *

Practical Mining, Civil, Mechanical,
Electrical Engineering, Metallurgy,
Cyanide Process, &c.
Surveying, Architecture, Drawing and Assaying.
933 MARKET ST. SAN FRANCISCO, CAL.
OPEN ALL YEAR
A. VAN DER NAILLEN, President.
Assaying of Ores, \$25; Bullion and Chlorination
Assay, \$25; Blowpipe Assay \$20. Full Course
of Assaying, \$50. Established 1864.
Send for Circular.

PETER HEER,

232-234 E. Washington St., - CHICAGO
Manufacturers of Highest Class

Engineering and Mining Instruments,
T-Squares, Triangles, Scales, Etc. Repairs carefully and promptly executed. Drafting Supplies of all kinds. Catalogue on application.



THE GRIFFIN MILL

The only Perfect Pulverizer Working both Wet or Dry Process

NO JOURNALS IN PULVERIZING CHAMBER.

Delivers a finished product. Will pulverize 1 to 2 tons per hour on Portland Cement, Quartz or ores depending on hardness of material and firmness of product.

— Manufactured and Sold by —

Bradley Pulverizer Co.,

92 STATE STREET,
Boston, Mass.

HADFIELD'S MANGANESE STEEL,

HARD, TOUGH.



Best Metal known for Stamp Shoes and Dies, Roll Shells, Crusher Plates and Side Liners. Toggles and Toggle Bearings, Gyratory Cones and Concaves or Liners, Mine Car Wheels, Coal Crushing Rolls, Etc., Etc.

TAYLOR IRON AND STEEL CO.,

Sole Licensees in America under Hadfield System and Patents.

High Bridge, N. J., U. S. A.

KEUFFEL & ESSER CO.
NEW YORK.
127 FULTON AND 42 ANN STS.
Branches: 131 Madison St., Chicago; 708 Locust Street, St. Louis, Missouri
Drawing Materials and Surveying Instruments
largest and best assorted stock in America. All requisites for field, mine, and draughting room. We have made a study of this line, and our goods are warranted to be as nearly perfect as it is possible to make them. Prices reasonable. Write for catalogue.

Agent FULTON POWER PUMPS

With Capacities up to 30,000 gallons per hour.
Made by A. T. Ames, of Galt, Cal.



Fred. F. Hunt, E. M.

Chemist and Assayer

Weighing, Sampling and Assaying all Mineral Products
Specialties: Lead, Bullion and Umpire Assays
Samples by Mail or Express.
77 Pine Street, New York City

LAMBERT

Gas, Gasoline and
Distillate Engines

TANKS, PIPE
and WATER
SUPPLY
GOODS



Call on or Address,

S. J. SMITH,

230 East Fourth Street,

LOS ANGELES, CAL.

Preach at 'Em!



If you want the Miners of North and South America to know you are on earth, you've got to "Preach at 'em."

The Mining and Metallurgical Journal

is the best medium to use—do all your preaching in it, and miners all over the world will listen to you.

OFFICES:

Stimson Block, Los Angeles and
64 Merchants' Exchange,
San Francisco, Cal.

KEYSTONE LUBRICATING GREASE

The only grease adapted to all temperatures. It will not splash or drip like oil.




Our goods are not for sale by the jobbing trade. If you want the genuine Keystone Grease it can only be obtained from us.

A full set of brass cups furnished FREE on first purchase

Especially adapted for Air Compressors and all kinds of Machinery in connection with Mines, Mills and Smelters. Send for trial sample and Cup Free of Charge.

Keystone Lubricating Co. 20th - Allegheny Ave.
Philadelphia, Pa.



The Harrington & King Perforating Co.

127 N. Union St., Chicago Ill.

Eastern Office, 284 Pearl St., New York.

ENTERED AT THE POST OFFICE AT LOS ANGELES, CALIFORNIA
AS SECOND CLASS MAIL MATTER.

F. W. EDELSTEN, Editor.

O. S. BREESE, Business Manager.

JOHN STEWART, Special Contributor.

ULRICH KNOCH, Publisher

OFFICES { Stimson Block, Los Angeles, Cal.
64-66 Merchants Exchange, San Francisco, Cal.

SUBSCRIPTION PRICE:

For United States, Mexico and Canada.....	\$2.50 per annum
" " " " " "	1.25 six months
All other countries in the postal union.....	3.50 per annum
" " " " " "	1.75 six months

100% SEMI-MONTHLY

ADVERTISING RATES FURNISHED ON APPLICATION.

For the first time the government of the United States has made the experiment of offering a loan to the people of the country. It was an offering of \$200,000,000, and was bid for more than six times the amount. The offerings in sums of \$500 and under absorbed the entire series. The bonds were issued in the sum of \$20, and in multiples thereof. The people put their savings into Uncle Sam's securities, rather than to hoard them or place them in savings institutions. The success of the scheme makes it improbable that the government will ever hereafter rely on rich syndicates to take its securities.

The issues being in small denominations—make it convenient to use the coupon bonds in ordinary business transactions, and operates as an increase of the circulating medium, and, consequently, as a stimulant to enterprise and commerce. The success that has attended the experiment suggests the wisdom of trying to refund all outstanding bonds as fast as possible into bonds of a less rate of interest and of small denominations, and the people may have the opportunity to absorb the whole indebtedness of the government. There is little doubt that the securities would be taken as fast as it is possible for the government to make the change.

The securities of Great Britain and France are not to any extent in the hands of foreigners but are held by their own people. The consequence is that the wealth of these nations is not depleted by the payment of interest to foreigners, while the people are taxed to meet interest charges, the money is distributed to their own citizens. It has been different in this country, as we have been paying interest abroad and reducing our own wealth or deducting from that which is annually produced. Another important feature is that a government which only owes its own people is stronger than one which is indebted to foreigners, for, to their patriotism is added pecuniary interest.

The embarrassments to both government and people in this country have proceeded from the fact that we have relied on foreign capital, not only to meet the demands upon government, but to develop our productive enterprises, the profits from which have largely accrued to the benefit of the foreign lenders and investors. These practices have continued as long as this country can stand it. The time has come when we should rely on our own capital, and it would be better to postpone enterprises for a time, and until

they can be undertaken with our own means, rather than to depend on aid from European money lenders, or those who seek investments in this country. When foreign money is being received and expended the situation is pleasing, but it is quite different when pay-day comes, and that day arrives every six months or a year, so far as concerns the payment of interest or dividends.

If a nation would be independent, it should avoid indebtedness to other peoples. There seems to be no need that we should contract foreign indebtedness hereafter in ordinary or perhaps under any circumstances. Our natural resources are so abundant, and the intelligence and energy of our people are so great that we can in future provide ourselves with all the necessary capital. Every year in which we keep our produced wealth to ourselves will give us enlarged financial strength, and enable us to do our own work with our own resources.

It has been said that "a public debt is a public blessing," which has been disputed as an abstract proposition, but, as we have a public debt, and one which will linger with us for an indefinite time, it presents an opening for the safe investment of the funds of minors, old people, and many other kinds which of necessity are held in trust. The surplus earnings in youthful and active days are so much stored labor, and Uncle Sam's treasury is a safe storehouse for it.

The successful experiment that has been made is likely to prove of incalculable value in many ways. We are about to enter upon a new century and a new era, a career of American independence, financial and commercial, as well as national and political.

According to the intentions of the objects of the association, as outlined in former issues of this JOURNAL, if carried out, may be made to work much good to the mining interests of the Western States. If, however, the chief object is to change our present federal mining laws, in respect to the most just provision contained therein—in allowing the prospector or miner to follow the dip of his vein or deposit parallel to the side lines of his claim to an unknown depth, then the proposed change will be a retrograde step, by changing to the square location of large area, and bounded by vertical side lines produced downwards from the said side lines of the square location.

The large extent of mineral development attained in the Western States and Territories has been gained through the wise provision of allowing the fullest scope to the efforts of the miner to develop his ore body in depth, under the law of the apex and extra lateral rights, and to depart from this just custom is to adopt a system which stops deep mining, and which is as fruitful of litigation and lawsuits as that now in force. As pointed out in this JOURNAL on former occasions, the error or evil does not lie in the boundaries of our mining claims, but in our wrong manner of settling mining disputes in courts of law by lawyers, whose chief business is to carry on the litigation for all there is in it for their own interests.

Our mining laws ought to be administered in each State and Territory by a Commissioner of Mines, and by each of the disputants naming an arbitrator who is a mining engineer to act for them, and, if necessary, with

power for them to name a third arbitrator. In this manner it is to the interests of these parties to obtain a settlement of the dispute, by taking the evidence on the ground and not in courts of law, and to act in the cause of justice to labor and capital invested in mining. As there is as much cause for dispute under the square location or that with vertical side line boundaries as under our present law, it is clear that it is our system of dealing out justice in courts of law that is at fault, and not the just miners' boundary, with side lines conforming to the dip of his deposit. To create a boundary which stops deep mining, and to say to the industrious miner who has developed ore in depth "thus far and no farther shalt thou go," is to stop industry and cause the worst form of monopoly to exist, and to give to another the reward earned by the investment of labor and capital in deep mining, and that is what the proposed change in side-line boundaries will do. Therefore, let side-line boundaries alone and change our wrong system of administering justice in courts of law to arbitration on the ground by mining men conversant with mining conditions.

The square location of large area is the system of surveying land in the eastern States, and is not a suitable or just system for the boundaries of a mining claim. Another important objection to it is that within its area are sure to be included more than one class of deposit or vein of ore. This rule holds true for the East as well as the Western States. Our present mining claim in the form of a parallelogram, of six hundred by fifteen hundred feet, containing 20.66 acres, is wide enough under our present law, and to increase the width is to include in it other minerals, or veins, or deposits, than that for which the location is made. The square location is found to be too large on that account in the Province of British Columbia, where it is now in force, and, for the last cause named, they desire to adopt a system somewhat similar to that of the United States. The fact is worthy of note, on account of a small minority in the United States who have had no experience as to its unjust operation to the miner to change to that form of location. As long as there are two veins or deposits running parallel to each other, of the same mineral or ore for which the location is made, it is not an exclusive grant of territory; but when another class of ore is found running parallel to it for which the miner has no use, then the large location prevents prospecting, and causes a monopoly of the undeveloped minerals. It is therefore not a mining condition in the interests of the largest amount of mineral development, and one which cannot be recommended on any cause but that of ignorance and monopoly.

The recording of mining work in most mines is a matter to which little heed is paid in the large majority of cases. This step is necessary both on account of the interest of the employed and the owner and manager. The intelligent understanding of the location and extent of the mine development by the workmen is highly important. To attain this object, a mine plan of the underground workings is instructive and useful, in addition to the office plan on paper. For this purpose such a plan should be placed at the

shaft house or hoisting works most convenient to the shaft or tunnel. A working plan of the shaft and each level of the mine can be made by taking two sheets of plate glass, which are supposed to represent the vein, and ought to be placed at the angle of the dip of the lode, and by painting on the glass with oil paint and the use of small pieces of wood, to represent timbers placed in the mine. A correct model of the shaft and level represented can be made, which can be colored to indicate the ground stoped, timbered, filled with refuse, as well as the ground unworked, with ore shoots or chimneys indicated, and so also with each succeeding level of the mine. By using sheets of plate glass of sufficient size, any desired scale can be made, and by the placing of the two sheets at the required distance apart from each other, a good model of the workings can be made.

Such a plan is of great service to the manager or foreman in giving instructions to the miners or timbermen, and in giving the employees a clear understanding of the location of the ore bodies and correct position of the workings.

KLONDIKE FAILURES.

As predicted in these columns in former issues, the return to the United States of many who went to the North Western gold fields some months ago, with ruined constitutions, and without the fortune, or often without their outfit and penniless, are evidences of the truth and sincerity of our warning remarks which were not heeded. If this suffering came on those alone who went there it would not be so severe, but when it falls to the lot of widows and orphans, the Klondike craze will have cost as much money and lost as many lives, in proportion to those engaged, as has the present war with Spain, and the gain will be as great to the general interests of the country.

THE WAR TAX ON STOCKS.

If this tax has the effect of weeding out all stock gambling operations in bogus mining ventures, which have their existence mostly on paper, and on which the location of the supposed mine itself has been known to change from one prospect claim to another a few miles off, as in the case of one notorious fake mining enterprise of recent date, it will have accomplished one good and in aiding those who staid at home, as well as adding power to the sinews of war. The mining industry can well afford to pay its share to the cause of liberty and justice to the oppressed colonial subjects of Spain, especially if that will increase the mineral area and foreign trade of the United States, of which the miners will get their share, and it may also help in giving additional territory to prospect, develop and supply with machinery, in place of our people going to seek misery and misfortune in the inhospitable northern wilderness.

SOME REMARKS ON THE CYANIDE PROCESS.

(Continued from July 15th issue.)

There is no more doubt that an ore crushed to as even a size as possible is much better leachable than an ore crushed into various sizes. Even a very finely powdered silicious ore can be leached successfully, if the size of the very small particles is more of an even

size. Ores crushed to different sizes do not leach so well, because the minimum particles will always fill out the minimum spaces left between the coarser particles, and render it, therefore, much more difficult for the solution to penetrate and come in contact with the gold-bearing particles of the ore.

On the Crown Reef mine, one of the best managed mines on the Rand, for instance, the ore is separated into two sizes and slimes, by means of Spitzkasten, after leaving the plates. Each size is collected in a different leaching vat and treated by itself. The extractions are very good, as shown by the following figures:

In February, 1895, 16,056 tons of ore were treated. 59.721 per cent pure gold of the assay value of the ore were recovered over the plates. The first size, being the coarser and more pyritic ore, amounted to 1057 tons. The residue of this size assayed 1.5 dwts per ton, after treatment by cyanide, and the amount of this gold recovered, 7.578 per cent of the assay value of the ore.

The second size, being the finer and more sandy ore, amounted to 10,152 tons, (residues assaying 0.87 dwt per ton, after treatment with cyanide,) fine gold recovered 17.829 per cent of the assay value of the ore. Slimes amounted to 4,847 tons, assaying 3.07 dwts per ton.

This gives a total actual extraction of 85.128 per cent on the assay value of the ore, and a loss of 14.878 per cent, of which however 3.687 per cent were contained in the slimes, of which again about 85 per cent were recovered by a process worked out and introduced by Mr. Williams; so that there was an actual loss of only about 7 per cent of the fine gold contained in the ore, or about 1.5 dwt per ton of ore.

Before referring now to the above-mentioned so called double treatment, I should like to quote a remark made by Mr. McArthur, at a meeting of the Society of Chemical Industry in 1890:

"Elsner has stated metallic gold dissolves in cyanide of potassium only in presence of oxygen. Not having seen the original account of Elsner's researches, I am not in the position to criticise his experiments, but I never could find that the presence of oxygen was necessary either to dissolve gold by itself or from ores by cyanide. If a piece of gold be immersed in a cyanide solution, so that air to act on it would have to penetrate two inches or three inches of the solution, the gold will dissolve in its usual slow and steady fashion. The equation shows that either oxygen must be absorbed or hydrogen evolved. I have seen no evidence of the former, and can adduce no proof for the latter; but I think the latter the more probable, because I cannot conceive oxygen penetrating even a film of cyanide solution without at once oxidizing the cyanide to cyanate, whereas in the other case, as suggested to me by my friend Mr. Ellis, the nascent hydrogen may be at once seized by the excess of cyanide present and ammoniacal compounds formed. However, we do not concern ourselves much with the reactions of pure gold, but as a matter of fact we cannot find that oxygen plays any part in the cyanide extraction of gold from ores. We have treated an ore with cyanide with free access of air, and then a parallel experiment was done with boiled water, the bottle filled to the stopper with solution and ore, and the stopper sealed. The extraction was the same in both cases."

Today no chemist is in doubt any more that Elsner's formula is correct, and that the

presence of oxygen is absolutely necessary for dissolving gold by cyanide. That this is so was proven by many experiments, of which I will mention one as a very striking one:

Take two small pieces of filter paper, put equal parts of precipitated fine gold in powder form on each of them. Make up a very dilute solution of cyanide into two beakers. Take one of the filter papers with the gold on it and put it in one of the beakers, but so that it floats on the surface of the solution only. Take the other filter paper with the gold on it and bring it into the second beaker, but so that it is covered by the solution at once. Allow it to settle to the bottom of the beaker, and if it does not do this by its own gravity, assist with a glass rod.

You will notice that the gold on the first filter paper will be dissolved in a few seconds, on account of the cyanide solution coming in contact only from below, while the gold itself is exposed to the oxygen of the air. The gold on the second filter paper, which lies at the bottom of the beaker, and which is perfectly covered by the solution, therefore not being able to come in direct contact with the oxygen of the air, requires hours before it becomes dissolved.

The practical confirmation of Elsner's theory has led to the so-called double treatment, which in fact is nothing but an oxidation process, in which oxygen of the air takes the part of an oxidizing agent.

To apply the double treatment, two leaching vats are placed above one another, so that the contents of the upper one can be easily discharged into the lower one, by means of Butter's patented bottom discharge. After the ore is charged into the upper vat, it is moistened with a dilute cyanide solution. After several hours the ore is discharged into the lower vat. By doing so, the ore moistened with the cyanide solution cannot help coming in contact with the oxygen of the air.

The practical result is that the first leaching, followed with a very weak cyanide solution in the second vat, gives the second solution by far the largest percentage of the gold contained in the ore solution. Practically, the formation of the double salt, gold cyanide potassium, had already taken place, and it requires only several washes with a very weak solution to extract the yellow metal.

Free milling sandy tailings do not require a double treatment. The oxygen of the air brought into contact with the ore at the same time with the solutions is sufficient in these cases.

The double treatment has been worked with very good results on pyritic tailings, and I do not see why it should not work well with a low grade pyritic ore as well.

In cases in which the gold contained in the ore is not very readily acted upon by cyanide, a so-called artificial oxidation may be applied with success. Experiments have proven that an addition of oxidizing chemicals accelerates the solution of the gold considerably. There can be no doubt that the oxidizing qualities of for instance permanganate of potash, ferri cyanide of potash, peroxide of sodium and other oxidizing chemicals may be of great advantage in extracting gold from pyrites and refractory low grade ores. It is certainly worth while in cases in which refractory ore is not tractable with success to make experiments in this line under the directions of a good and competent metallurgist.

I have perfect confidence that the extraction of gold from ores by cyanide will increase in this country for a good many years

to come, and that many lowgrade gold ore deposits, which were regarded as not payable heretofore, will become possible to be developed and worked successfully by the cyanide process, the process by which it became possible to increase the gold output of the whole world considerably, and which is one of the reasons that the United States take the lead today of all gold-producing countries, and which let us hope will be the case for many years to come, to the certain prosperity and high commercial standing our country takes today amongst the countries of the whole world.

To give a very good example in order to show how important this question of crushing the ore to its proper size for leaching purposes with Cyanide solution is, I only need refer to what occurred some years ago at the now world renowned Mercur Mine, not very many miles away from here. At that time, six to seven years ago, the former managers of this mine and Cyanide extraction plant, which by the way, was the very first plant for treating ore in this country by the so-called direct Cyanide process, were advised to grind the ore to a size of about 600 mesh in order to attain the highest possible extraction. The result was an extraction of only about 40 per cent of the assay value of the ore. This for some time proved quite a puzzle and was of great trouble to the managers. After many and not very successful experiments had been gone through, it was decided not to crush the ore so fine on account of the porous nature of the ore and its considerable percentage of Talc and Alumina, which latter of course rendered the ore rather impenetrable for the Cyanide solution. The results were, that the coarser the ore was crushed the higher the extraction became, and today, while the ore is crushed only to the size of about $\frac{1}{4}$ -inch square, one of the highest extractions known, about 85 per cent of the assay value of the ore, assaying on the average 15 to 18 dwts. per ton is gained.

During my last stay on the Rand in 1895 to 1896 I had the opportunity to convince myself that the classification and separation of the ores, according to size and specific gravity, before the treatment with Cyanide, was a great success. On my visit to the Transvaal in 1895 three processes were in use to recover gold from ore. First, Amalgamation over copper plates, by which most of the free milling ore was recovered (about 50 per cent of the assay value).

Second, subsequent chlorination of the concentrates from Frue vanners, and

Third, Cyaniding of the remaining tailings.

In 1897 the total output of the mines on the Rand amounted to over three million ounces fine gold, of which one-third, say one million ounces, were recovered by the Cyanide process. That the amount of gold recovered by Cyanide has increased so considerably during the last years and that the Cyanide process has become quite a strong competitor to the chlorination process on the Rand is mostly due,

First, to the above-mentioned classification of the ore, and

Secondly, to the so-called double treatment of the ore.

I thought it well to say a few words about these two processes as in some cases they may be applied with advantage in this country. They may either help to increase the extraction or may lead to the successful treatment of ores which were not treatable before. On the Rand it was proven that,

First, a decided separation of the sandy ore from the slimes is necessary in order to obtain a good extraction.


Secondly, that by classifying a concentrated ore into different groups of different sizes and specific gravity a much higher extraction is gained.

This separation and classification of the ore is done by passing the ore as it comes from the plates through a system of so-called Spitzlütten and Spitzkasten, apparatuses well known to all of you and which I therefore do not think necessary to describe in detail.

(To be continued.)

Barnes' Upright Drill.

A new drill, which W. F. & John Barnes Co., of 105 Ruby street, Rochford, Ill., has just built and are placing on the market, is the Barnes Upright Drill, No. 5, with 26 inch swing. It was produced in response to a very general inquiry for a sliding-head drill smaller than their 28 inch drill and it is thought this new machine will meet fully the requirements for a drill intermediate in size and capacity between the 25 inch stationary head drill and the 28 inch and 34 inch sliding head



BARNES' NO. 5 UPRIGHT DRILL.

drills. This new machine has been designed with special care, and it is believed to embody every feature necessary to make it a complete and perfect tool. The workmanship is thoroughly first-class in every respect.

The feed arrangement is specially strong, and provides for all the different feeds which can be used on a drill press. The cut shows very clearly the feed mechanism, and, as will be seen, the drill has power self feed with automatic stop, lever and worm feed, and quick return for spindle. The feature of hand lever feed on a sliding head drill, in combination with worm and power feed, is new and increases the usefulness of the drill. The spindle is fitted with the No. 3 Morse taper.

The dimensions are as follows:

Height of drill.....	7 ft.
Greatest distance from spindle to base..	53 in.
Minimum.....	21 in.
Diameter of column.....	7 in.
Diameter of spindle.....	1 11-16 in.
Width of column face.....	6 in.
Travel of sliding head.....	21 in.

Travel of spindle.....	11 in.
Diameter of large pulley on cone.....	10 in.
Diameter of small pulley on cone.....	4 in.
Face of pulleys.....	3 in.
Tight and loose pulleys.....	10x3 in.
Diameter of crown gear.....	7 1/4 in.
Diameter of bevel pinion.....	3 3/4 in.
Face of tooth.....	1 3/4 in.
Ratio of back gearing.....	5 1/2 to 1.
Required floor space.....	21x52 in.
Weight.....	1350 lbs.

In our issue of July 15th, on page 8, in our review of the second edition of *Gas, Gasoline and Oil Engines*, by G. D. Hiscox, we neglected to give price of same, which is \$250. The publishers, Messrs. Norman W. Henley & Co., of 132 Nassau street, New York City, will forward the book to anyone on receipt of price.

The Consolidated Kansas City Smelting and Refining Company have met with phenomenal success in marketing their new bi-product, the Alchemist brand of blue vitriol. In November of last year they improved their copper plant in many ways, increasing their capacity to 550 tons of blue vitriol per month.

The present year was started under the most auspicious circumstances, as they were awarded the entire contract for the consumption of the Western Union Telegraph Co. A good market has been found in the East, Old Mexico and Canada. Several shipments have also been made to the Mediterranean coast. The Alchemist brand of blue vitriol is put on the market in the form of large and small crystals. Its great popularity is due to the high percentage of copper, and to the almost entire absence of impurities.

The Colorado Iron Works Company are working their plant to its full capacity, and making shipments to nearly all parts of the world. Among recent shipments were two 42x144 silver-lead smelting furnaces, with complete smelting equipment, to the Tasmanian Smelting Company, located on the Island of Tasmania. This order filled six cars. This company is also building a 42x144 silver-lead smelting furnace, for the Hanauer Smelting Company, of Utah; and a 45x144 silver-lead smelting furnace, for the Germania Lead Works, Salt Lake City, Utah; both with complete smelting equipments. A large jacket smelting furnace for the Canadian Pacific R. R., British Columbia; one for the Great National Mexican Central Smelting Company, Old Mexico, and one for the Mountain Copper Company, in California.

This firm has established a reputation for its smelting furnaces because of superior design, workmanship and material, which brings orders from all over the world.

The name of the crude mill for crushing ore, the correct orthography of which is "arastre," is written and pronounced in many different ways, some of them amusing. The senior editor of the *Transcript* once wrote a letter for publication in the east, from a mining camp in the Death Valley region, in which he mentioned a "raster." He got the name by ear, from an experienced miner, and being a hundred miles from any kind of written authority, so wrote it.—*San Bernardino Transcript*.

While *The Transcript* devotes considerable space to mining news, and furnishes some first class mining literature, it is apt to be mistaken. If the senior editor of *The Transcript* will look farther into the matter, he will find that he has not spelt the word rightly as yet.

THE PROVO-MERCUR 40,000 VOLT TRANSMISSION.*

BY LEON W. BLY.

But few, even in the electrical transmission fraternity, are aware of the fact that the highest voltage employed in the commercial transmission of power over a long distance is that which is now operated on the lines of the Telluride Power Transmission Company between Provo canyon and Mercur, Utah. The Telluride people are pioneers in the field of extremely high voltage transmission and for several years have experimented conjointly with the Westinghouse Electric and Manufacturing Company, on transmission lines with potentials ranging as high as 120,000 volts.

The line used for carrying out these experiments was a special one extending from the Telluride Company's power house near Ames, Colorado, to the Gold King mine and having a length of 11,720 feet. The route of this line was over a rugged country subject to a heavy fall of snow in winter and rain with severe lightning in the summer. The poles were placed one hundred and eighty feet apart and supported three circuits of No. 8 galvanized iron wire. Practically all the different varieties of cross arms, pins and insulators to be found on the market were tested, as were also many new models of these appliances, devised at the time, and during the test runs, the condition of the atmosphere and of the line in regard to snow, rain and humidity were carefully noted. Up to the present, the results of these important experiments are reserved and every effort to secure the data deduced has been unavailing.

Reverting to the Provo-Mercur transmission, the plans of the Telluride company contemplate the early installation of two thousand and horse power in two units of 750 kilowatts each, to furnish power and lights to the mining interests in and about Mercur and Tintic, Utah. These two districts, which are perhaps twenty miles apart, are respectively thirty-two and forty-six miles from Provo Canyon, where the power house is located.

*Journal of Electricity.

The Provo-Mercur transmission line is the one which has been placed in operation, but work has been commenced on the construction of the independent line from Provo Canyon to the Tintic district, which will be, as stated, forty-six miles in length. After the Provo-Tintic line is completed, the substations at Mercur and Tintic will be connected together by a subsidiary transmission line so that in case of accident to either main line from Provo, service may be continued without interruption to both places. Immunity from pole line trouble seems to be perfectly secure by this arrangement as the two pole lines takes entirely different routes.

At present, one 750 kw. type "A. P." three phase General Electric generator is being operated by a flexible connection to a turbine wheel driven under a head of 125 feet and running at 300 revolutions, the turbine being temporarily hand-regulated. This generator has a periodicity of sixty cycles, is star wound, and gives a phase potential of 800 volts. Of the four 250 kw. raising transformers installed in the generating station, but three are in use, the remaining one being as reserve, and its connections are so arranged

that it can be substituted in service for either of the other transformers at a moment's notice. The normal primary potential applied to the raising transformers is 462 volts, the normal secondary being 23,100 volts. As is the case with the primaries, the secondaries are connected in star, hence the three-phase high tension terminals have a phase pressure of 40,000 volts.

The principal material



BREAK SWITCH FOR 40,000 VOLTS ON THE PROVO-MERCUR TRANSMISSION.


used in the insulation of these high tension transformers is muslin and fullerboard, blocks of maple wood being used to separate the coils. The transformer cores and coils are immersed in mineral seal oil, with no other cooling device than that of the natural radiation of heat from the surfaces of their cases. This radiation is, however, very great because of the fact that the surfaces of the cases are rather deeply corrugated. To be exact, the corrugations are $2\frac{1}{4}$ inches deep and one inch wide. The general appearance of the high tension transformers is shown in the illustration appearing on page 11, which also shows plainly the method of supporting the interior high pressure circuits.

The high tension leads are brought out of the tops of the tanks through walnut bushings, on the inside of each of which is a heavy porcelain tube extending from the top of the bushing down into the tank beneath the surface of the oil. The low tension leads are brought out at the sides of the tanks and these low tension leads consist of two series of twenty-eight turns in multiple of two three-quarters inch by 349 mils strap copper. The high tension windings consist of 1400 of No. 9 magnet wire. These transformers, as well as the lowering transformers at the Mercur sub station, were built by the Wagner Electric and Manufacturing Company of St. Louis, Mo., upon the designs and specifications of the Telluride Power Transmission Company.

Tests made by the writer show the copper loss of the transformers to average about 2150 watts; the iron loss is about 3030 watts; the normal temperature at full load is 118 degrees above that of the surrounding air.

Three phase generation, three phase transmission and two phase distribution constitutes the scheme of the polyphase equipment, and all the three phase portions are star connected and the common center or neutral point of the star is grounded as will be described later. The line is protected by the Wurts non-arcing lightning arresters.

The line, which is carried on 35-foot cedar poles placed 125 feet apart, is of No. 5 B. & S., medium hard drawn copper, supported so as to form the points of an equilateral triangle



FUSES, CHOKE COILS AND LIGHTNING ARRESTERS ON THE PROVO-MERCUR TRANSMISSION.



THE 40,000 VOLT TRANSFORMERS.

having six-foot sides. One of the three wires is placed on top of the pole and the remaining two are run on the respective insulators of a seven-foot cross arm with a separation of six feet between the pins. The wires are not transposed, and a metallic telephone circuit is carried on brackets at a distance of 42 inches below the cross arm.

The insulators are of a special type of triple petticoat glass, having two corrugations around the top below the groove designed to carry the line wire. This arrangement not only has the advantage of increasing the surface of the glass between the wire and pin, but it also protects a portion of the surface from extreme moisture during rain storms. The approximate dimensions of the insulator are $6\frac{1}{2}$ inches across the base by 6 inches high, and the insulator is supported by a specially long locust pin made proof against moisture by being boiled in paraffine. Great care was taken to fill the pores of the wood thoroughly, to effect which the pins were kept in the tank in which they had been boiled until they had become thoroughly cooled, after which the surplus wax was removed and the surface of the pin was made smooth by dipping it again in very hot paraffine wax. These pins, being extra long, supported the insulator clear of the cross arm by five inches and the pin used at the top of the pole is two inches longer still, making the separation between the top insulator and the pole to be seven inches.

It appears obvious that an insulator of this design will offer a high resistance to a discharge over its surface, but should it be assumed that it could reach the lower edge of the outside petticoat, there would be little inducement for it to go further as the pin is at all times a good insulator and its surface is of such a nature that a film of moisture will not collect over it. On several occasions insulators have been shattered by marksmen, but it has been the experience that if trouble developed, owing to the grounding of the wire on the pin or cross arm, it would promptly rectify itself by the burning off of the cross arm, leaving the wire without support at that pole.

It will be interesting to note that at each pole along the line one can hear crackling from static discharges at all times, and during certain atmospheric condition the insulators are dimly luminous with pale phosphorescence. The

line itself, however, is non-luminous at all times except for the brush discharges which sometimes exist from points of the line, such as from the tips of the tie wires.

The lightning arresters, as before stated, are of the Wurts type. About twenty-five arresters being kept between the line and the ground. Six choke coils are used, and these are placed edgewise on top of the arrester racks, and as the latter are designed to be as compact as possible, they measure over all but two feet, by $3\frac{1}{2}$ feet, by 7 feet high. One of these banks of lightning arresters and choke coils are connected in each line wire as shown in the illustration.

To be more explicit, the connections of the lightning arresters are arranged as follows: Six choke coils are coupled in series and cut into the line after leaving the transformers. For convenience, we will here designate the choke coils by numerals consecutively, coil number 1 being at the left and being connected direct to the line. On the left side of each coil, numbered 1 and 2, three Wurts arresters, each containing seven nonarcing cylinders, with about one-twentieth inch gap, are tapped off in series, there being thus two series of three arresters each, for the first two coils. The free ends of the two series of arresters from coils numbered 1 and 2 are closed together, the connection thus formed being termed "point a." Similarly the two series of arresters from coils numbered 3 and 4 are connected at point b, as are also the two series of arresters of coils 5 and 6 at point c. From points a and b are then carried a single series of five arresters, the ends of these series being joined at the point d, while from point c is run a single series of eight arresters which are connected to (at point e) the terminal of a single series of three arresters between d and e. Eleven choke coils therefore, intervene between point e and either of the six choke coils referred to, while from point e is continued a single series of fourteen arresters running to ground. About twenty-five arresters intervene between any choke coil and ground while a minimum of six arresters are across a coil.

Two further features of interest, also shown in the engraving last referred to, are found in


the fuses inserted in the high tension wires, and in the high tension switches used. Each of these three fuses consists of a single number 30 B. & S. bare copper wire, thirty-six inches in length, over which an asbestos tube is drawn. The fact that three such thread-like wires will carry a load of over seven hundred horse power, is as incredible to the layman as it is evident to the electrical engineer, who fully realizes the significance of transmission at a potential of 40,000 volts.

The high tension switches, illustrated on page 10, are inserted on each of the three line wires. They are rigidly connected together, so as to be operated by a common switch bar as shown, and each give to a six-foot break, the separation between the switches being five feet.

The substation now in operation is installed in the Golden Gate mill, at Mercur, which is believed to be one of the largest, if not the largest, cyanide mill in the world. Its electrical equipment, aside from the induction motors used for mining and milling purposes, and as about to be described, consists of three, 300-kw. lowering transformers, by means of which the 40,000 volt three phase line current is reduced to 220-volt, two phase current, used for lighting and for operating Westinghouse two phase type "C" induction motors. The plan of connections for the step-down transformers is shown in the sketch "outline circuits," which is a comprehensive outline drawing of the electrical connections of the entire equipment from the generator to the ultimate motors and incandescent lights operated by the system.

These lowering transformers are the same in general design as the raising transformers in the power house at Provo Canyon, and differ therefrom only in capacity and voltage. It will be noticed, too, that, as in the case in the generating station, an extra transformer is installed for emergency use, and its connections are so arranged that it can be substituted for either of the other lowering transformers with celerity.

The transforming of three phase current to two phase current, and vice versa, by two transformers, is generally understood, and will therefore not be taken up. As previously stated, the neutral point of the three phase system in both the generator and the high tension side of the raising transformers are grounded, and the practice of grounding is carried out even in the low tension distribution circuits in the manner to be shown.



OUTLINE CIRCUITS OF PROVO-MERCUR TRANSMISSION.

The neutral point of a three-phase circuit, in a three-phase two phase transformer, may be determined graphically by erecting the perpendicular ba from the center of the side cd of the equilateral triangle shown in the corner of the plan herewith of circuit connections, and upon this perpendicular, ba , locate the center of the triangle, as shown at the point e . Let the line ab represent the 100 per cent side of a three-phase two-phase transformer, when the line ec will represent the 86 per cent transformers, and the point e will be one-third of the length of the line ba measured from b . It is at this point that the tap for the ground is brought out, and it is located in the three-phase two-phase transformers at one-third of the turns of the 86 per cent transformer, from the side connected to the center of the 100 per cent transformer.

The 220 volt secondary is also grounded through incandescent lamps, as shown at C , where two 110-volt lamps are connected in series between either of the three wires of the two-phase distribution, and the ground. Moreover, a tap is brought out from the center of each of the three phases comprising the two-phase system, and this tap constitutes the neutral wire of the Edison three wire system, which is used at Mercur for incandescent distribution service. Lighting service is taken from both transformers, great care being exercised to keep the entire system balanced, not only as an Edison three wire system, but also to keep each of the two phases balanced with the other. The thoroughness with which the various portions of the high tension three phase system is grounded, as well as the effectual grounding of the 220-volt system, leads to the belief that no danger from shock is presented.

A further feature that will excite surprise is the fact that current is carried from the lowering transformers to the center of distribution in the Golden Gate mill and hoist house by a three-conductor concentric cable, each of the three conductors having a sectional area of 1,000,000 circular mils. The length of this cable leading into the mill is 220 feet, and from its terminal is tapped off leads for six induction motors, consisting of one 150 hp. operating rolls, etc.; one 50 hp. motor operating the roasters; one 30 hp. motor operating pumps; two 15 hp. motors operating blowers, and one 10 hp. motor in the machine shop. The length of cable leading into the hoist house is about 60 feet, and from its terminal is tapped off leads for three motors, consisting of one 150 hp. and one 75 hp. motors operating hoists and one 100 hp. motor operating an air compressor.

Two other motors, each of 50 hp. operating rock crushers, are run on independent leads from the transformers, and these complete the plant.

ELECTROLYTIC REFINING OF LEAD.

BY SHERARD COWPER-COLKS, M. I. E. E., A. M. I. C. E.

Lead, when recovered from its ores by smelting, is obtained as a crude metal, the so-called work lead, which has to go through a refining process in order to obtain soft or market lead. Work lead is obtained either by roasting reactions, by reduction, or by the precipitation process. Refining is effected either by oxidation after fusion or by electrolysis. Lead is never obtained pure when smelted from the ore. It is almost always alloyed with all the other metals contained in the ore itself. Apart from the fact that the useful properties of the metal are affected by

these other metals, it is, of course, advisable for economical reasons to recover the precious metals present, such as silver.

One of the first processes worked on a commercial scale for the electrolytic refining of lead by electrolysis was that of Keith. In this process the crude or work lead is melted at the lowest possible temperature in iron kettles from which it is tapped into molds. The anodes thus produced are fastened to metal rods by suitable clamps, and enclosed in close-fitting bags of coarse muslin. The electrolyzing cells are made of wood or iron; the cathodes are thin metal plates attached to rods in a similar manner to the cathodes. The electrolyte is composed of lead sulphate dissolved in an aqueous solution of acetate of sodium; it is made by electrolyzing with lead anodes a mixture of $1\frac{1}{2}$ lbs. of acetate of sodium, $2\frac{3}{4}$ ounces of sulphuric acid and 1 gallon of water, and is heated to 38°C . The sulphuric acid attacks and the acetate dissolves the lead, zinc and iron of the anodes. The zinc and iron, being electro-positive to lead in the liquid, are less easily reduced to metal and accumulate in the solution, and when dissolved in considerable quantity are, to some extent, deposited as oxide on the cathode, the current density employed being about 1.86 amperes per square foot. The lead which is deposited on the cathode is crystalline in form and separates continually from the plates, a space being left in the cells for its accumulation. When the anodes have been dissolved, the bags suspended from their supporting rods are carried to a reservoir and the residual solid matter from the plates is washed and returned to the melting kettles. The slimes suspended from the wash water are allowed to settle, the water is drained off, and the residue filtered. The slimes usually contain antimony, arsenic, silver, copper, gold and iron. A process that has been recently tried on a commercial scale is that of Tommasi. In this case, the electrolyte is the double acetate of lead and potassium (or sodium), the anodes are crude argentiferous lead, and two of these are opposed to a copper or aluminum alloy cathode, which is in the form of a disk rotating at the rate of from one to two revolutions per minute.

These disks are about 10 feet in diameter and three-quarters of an inch thick and are half immersed in the liquid. At the upper part are scrapers which serve to detach the small spongy crystals of lead which form during electrolysis. The crystals when removed fall into channels which convey them to a sieve of wire gauze where they are drained and washed, the wash water being concentrated by evaporation to 20 Baume (sp. gr. 1.256) and used again in the electroplate. The lead is then compressed and mixed with 2 or 3 per cent. of charcoal powder and fused. The silver, with most of the arsenic and antimony is separated at the anode, and is collected in trays to be fused subsequently with sodium nitrate and a little borax, by which the silver is separated from the arsenic and antimony.* The cost is estimated by the inventor at from 8 to 10 francs per ton of lead when steam power is used. When lead acetate is used as an electroplate, the resistance is found to be lowered, which is probably due to the prevention of lead peroxide deposits upon the anodes, which must be at the expense of the organic substance itself which becomes slowly and surely oxidized. The products of the oxidation of acetic acid are carbonic acid gas

and water, which are of no intrinsic value, this being the case, the acetic acid becomes an expensive electrolyte as it has to be constantly renewed. The lead peroxide formed at the anode is reduced by a portion of the organic acid to oxide, which then dissolves in the acid and becomes finally reduced to metallic lead at the cathode. The impurities present in the crude metal and the oxides on the face of the anodes are usually bad conductors of electricity, and, if they do not become detached from the anodes, they form an insulating coat over a large portion of the anode surface. The natural consequence of this is that the current passes mainly through those parts of the plate that remain freely exposed, and so the current density becomes greatly increased at these portions with the result that the anode is rapidly riddled with holes. The addition of fluid carbonic acid when mixed gradually with sulphuric acid, and digested for some time at a temperature of from 50 to 100°C . easily converts it into cresol sulphuric acid, which is soluble in water, and is capable of forming soluble salts with lead. These salts have been successfully used for the deposition of lead.

Maxwell Lyte has suggested converting the lead into chloride and electrolyzing it in the molten condition. Crude lead is fused and oxidized by a blast of air in a converter, the oxide is then stirred with hydrochloric acid in earthenware vessels until it is converted into chloride. Any silver compound associated with the lead, salt or oxide treated, is chloridized and is extracted from the mass by the application of strong hydrochloric acid or brine.

Concerning Chlorination.

VANCOUVER, BRITISH COLUMBIA, July 13, 1898

TO THE EDITOR
MINING & METALLURGICAL JOURNAL,
Scribner Block, Los Angeles, California.

SIR:—When pointing out the error in the description of the Chlorination Process, I omitted to give the equation showing the reaction which takes place when the lime chloride (not lime, as inadvertently stated by me) is acted upon by hydrochloric (muriatic) acid as follows: $\text{CaOCl}_2 + 2\text{HCl} = \text{CaCl}_2 + \text{H}_2\text{O} + \text{Cl}_2$.

Yours faithfully,
(Signed) J. O'SULLIVAN,
Chief Assayer and Chemist, The British Columbia Agency Ltd

While hydrochloric acid and chloride of lime are used in chlorination processes, the combination is not received with as much favor as the combination of sulphuric acid and chloride of lime, $\text{CaOCl}_2 + \text{H}_2\text{SO}_4 = \text{CaSO}_4 + \text{H}^+\text{O} + \text{Cl}_2$, for the reason that the difference in price of sulphuric acid and hydrochloric acid which is as about 10 to 19 in favor of sulphuric acid, or nearly one half less. Of course, we have to take into consideration that it requires more sulphuric acid than it does hydrochloric acid to do a stipulated amount of work, about as 73 to 98; in other words, 73 parts of hydrochloric acid will do as much work as 98 parts of sulphuric acid, but it can be readily understood that the difference in price more than balances the difference in quantity.

The fact of the matter is hydrochloric acid is principally used in laboratory work, and seldom on a commercial scale for the treatment of ores.

Due principally to the fact of concessions made by the smelters and railroads, and the leasing system now in vogue, also to the new mills and concentrators that are being erected, many of the mines which could not have been operated after the panic are now in a position to make a profit.

*The arsenic and antimony are oxidized to the maximum and unite with the soda to form soda.

THE ELECTRO-CHEMICAL INDUSTRIES OF ENGLAND.

JOHN R. C. KERSHAW, F. I. C.

Twenty years ago the industrial applications of electricity in Europe in the domain of chemistry and metallurgy were limited to two manufactures—that of electroplate, a business in the hands chiefly of the famous Birmingham firm of Elington Bros., and that of refined copper. The latter industry was carried on upon a very small scale of operations, and the combined output of the Pembrey and Hamburg refineries—the two largest at this date—did not much exceed 1,000 tons per annum, while the total number of refineries in Europe was only six or seven.

Ten years later, electro-plating and copper refining were still the only two electro-chemical industries. But the latter industry has steadily increased in Europe under the stimulus of the demand created by electrical engineering for the purest form of copper, and the electrolytic method of copper refining had been introduced into the United States by the Balbach Company of Newark and by the Baltimore Smelting and Refining Co. At this date there were four electrolytic copper refineries in operation in England, with from eight to twelve scattered over the Continent of Europe.

The progress that has been made since 1885 has however been remarkably rapid, and while ten years ago there were many who believed electricity would have but a very minor role to play in the chemical and metallurgical industries, the enormous expansion of the electrolytic copper refining industry, and the marked success which has attended the use of electrolytic methods in the manufacture of aluminium and chlorate of potash, have now reduced the number who hold this belief to a very small minority of the community. This change in the views of practical men with regard to the possibilities of electricity as an agent for promoting chemical reactions upon a manufacturing scale, is due to the rapid growth of the past ten years.

There are now no fewer than eighteen distinct electro-chemical or electro-metallurgical manufactures carried on in different parts of Europe and America in over 150 manufacto-

*Electricity

ries, while the production of one article—electrolytic copper—has increased from between ten to twenty thousand tons in 1887 to over 150,000 tons in 1897—that is, to an amount nearly equal to one half the total copper production of the globe.

This progress would have been impossible except for the cheapened sources of electricity that are now available when current is required in large quantities.

The experience gained in the period 1880

1890, when electric lighting was absorbing all the attention of electrical engineers, has led to valuable improvements in the efficiency of both engines and dynamos, and the more recent development of large water powers for manufacturing purposes has still further tended to reduce the cost of electrical energy. This is today being produced for manufacturing operations at a cost which twenty years ago would have been considered below the limits of possibility.


Great as the electric lighting industry has become in both Europe and America, there are only a few lighting installations in either continent with a dynamo capacity equal to that of some of the larger and more important industrial undertakings of the character now under consideration.

In these electro-chemical industries, single power plants of between 2,000 and 4,000 H.P. are common; and the greater portion of the power to be developed from the numerous water falls of both the New World and the Old will undoubtedly find utilization in these comparatively new industries.

In England, owing to the lack of large natural water powers suitable for industrial development, the electro-chemical developments that have occurred have with two exceptions had to depend upon coal for their supply of the electric current; and two of these undertakings possess steam plants of the most modern description for generation of their electrical energy.

The Castner-Kellner Alkali Co.—Two views are given of the works of this company at Weston Point, Lancashire. The company was formed in 1896 with a capital of \$1,440,000 and the manufacture of caustic soda and bleach by the first 1,000 H.P. installment of plant was commenced early in 1897. The results of the working of this plant have been satisfactory, and the extension of the works to the originally designed capacity of 4,000 H.P. is now proceeding. The shares of this company were quoted at a premium at the commencement of the present year, a fact that speaks well for the confidence of the investing public in the future of the undertaking. The process depends upon the decomposition of a solution of common salt by means of the electric current, mercury being used as cathode material and carbon for anodes. By a mechanical device the cells are subjected to a periodical tilting movement which brings the sodium amalgam formed at the cathode into contact with water, and, whilst regenerating the mercury for use in the cathode compartment of the cell again, produces a solution of sodium hydrate practically quite free from sodium chloride. The chlorine liberated at the carbon anodes is conducted away, and is used in the ordinary manner for the manufacture of bleaching powder.* The English Castner-Kellner Company has made a deal with the "Deutsche Solvay Werke Aktien Gesellschaft" whereby the latter company has undertaken to accept delivery of the whole of the bleaching powder product at Weston Point during three years at a fixed price. This arrangement of course gives stability to the position of the Castner-Kellner Company and ensures a market for its products. Owing to the output of bleaching powder by this company and by the other electrolytic alkali company at St. Helens, the market price of 35 per cent. bleaching powder has already dropped about \$5 per ton, and a further fall may occur during the present year. Some difficulty has arisen, it is believed in the conduct of the electrolytic process, due to the impurities of the brine pumped from the Cheshire salt mines and the second 1,000 H.P.

For further details of this process, see *Electricity*, September 5th and 12th.



CELL ROOM IN THE CASTNER-KELLNER ALKALI WORKS, WESTON POINT, ENGLAND. CAPACITY 1,000 H. P.



ENGINE AND DYNAMO ROOM OF THE CASTNER-KELLNER ALKALI WORKS, WESTON POINT, ENGLAND.

installment of plant is to be used for the production of caustic potash from Stassfurt potassium chloride. It may interest some of our readers to know that this process is now at work at Niagra in the factory of the Mathieson Alkali Company, and 1,500 HP. is now utilized at this spot in the production of caustic alkalis and chlorine products. A minimum royalty charge of \$19,200 per annum is to be paid by the Mathieson Company to the Aluminum Company of Oldbury, England, who at the date of this agreement were the owners of the American rights of the Castner-Kellner process.

CORRESPONDENCE WISCONSIN.

WEST SUPERIOR, WIS., July 21, 1898.

EDITOR JOURNAL:—The North Wisconsin copper mine, of Douglas Range, 15 miles south of Superior, has arranged to continue the development work begun last fall. The 16-foot amygdaloidal vein carries 1 to 2 per cent native copper. The company has sunk 64 feet on the vein, and has drawn a shaft of drift 26 feet along the vein. Several other pits have been sunk on the property. Considerable interest is shown locally on the formation, and much prospecting has been done the whole length of the range, which discloses at many places promising outcroppings of cupriferous rock; the formation extends in an east and west direction across Douglas County, Wisconsin, and is exposed again southward from the Michigan line to Minnesota.

KIRBY THOMAS.

Miscellaneous Mining News.

ALASKA.

In a letter to a Southern California mining man an assayer writes: "Sunrise City is at the head of Cook's Inlet, and there are a lot of people here but few miners, and the majority are waiting to get back to the States. They can't find gold on the bushes and have to pack everything on their backs in going about, and this makes calamity howlers out of most of them pretty quick. The company I am with has bought two claims for \$3,000. They are considered among the best here. I have been prospecting them for the past ten days and they prospect pretty well all over. I can make \$5 per day and not reach bedrock. Bed-rock is about 17 feet from the surface and both claims can be worked without hindrance from water."

ARIZONA.

From Big Bug.

The Little Annie has stopped most of her work until an air compressor and Burleigh drill can be obtained. Then the Providence Mining Co. will prospect the entire Annie mountain. This company is thinking of placing a smelter about a mile down Big Bug from their mine.

Mr. Kent and son, owners of the Lottie and Postmaster mines, are expected from the east in a few days. Mr. Kent is now having a tunnel run 600 feet through the mountain in order that the Lottie mine may be drained of its water. This tunnel is now about 400 feet long and six men are constantly at work on the east end of it.

The Henrietta mine has been taken in charge by Mr. Henry, who will pay the indebtedness on this mine and again resume work.

The Swindler mine, owned by Mr. Brindley, was bonded to Mr. Shirley July 15 for an unknown amount, but it is to be paid at the end of six months.—*Arizona Republican.*

CALIFORNIA.

KERN COUNTY.

The famous Long Tom property, near Bakersfield in Kern county, was recently sold to a Pittsburg syndicate for \$160,000.

J. W. Waltham has taken a bond on the Golden Bar mine, and has already installed a gasoline hoist and very systematic prospecting work will be done. A new innovation in the methods of mining in this camp will be introduced in the shape of a female engineer. Mrs. Waltham will have charge of the hoist and a general superintendence of the mine. As she adopts while on duty the regulation overalls of our profession, us "Hardrockers" extend to her the glad hand and wish her luck.

The most important find in the camp so far has been the new strike of sulphuret ore in the Little Butte, at a depth of 500 feet. The ore body shows a five foot vein of dark, close-grained, bluish-looking quartz and mills about \$15 free gold with the sulphurets worth about \$88 per ton. More than anything else it shows the permanency of the ledges as for the pitch of the ore chute the same vein passes under the Kinyon and Wedge only at a greater depth. The Little Butte people are feeling mighty good over their prospects and employes take renewed courage.—*Miner.*

LOS ANGELES COUNTY.

The reorganization of the Red Rover Mining and Milling Company has taken place, and preparations for the commencement of active operations on the Red Rover mine at Acton have been made. The former superintendent, Mr. Gilbert, said there was a considerable quantity of ore in the bottom of the sixth level that would mill between \$5,000 and \$6,000 per ton. The mine is well developed and has a fine plant of milling machinery, besides an extensive water works plant, all of which has been paid for from wealth taken from the mine. The company is about to put in a still larger water works on Gleeson Mountain, and expect to supply the town of Acton with water.

Frank McCann and others are about to erect a cyanide plant on Gleeson Mountain, to do custom work. The whole of the Cedar Mining District is known to abound in cyaniding ores, which, with a plant to work them, will bring that section prominently to the front.

RIVERSIDE COUNTY.

The stamp mill at Dale City, belonging to Ingersol, Esler & Reitz, is now erected and began to stamp ores this week.

H. C. Steele of the Desert Queen mine has returned to the city on account of illness. The work on the mine still continues.

The tailings of the Desert Queen mine will be cyanided in the tanks of the Old Virginia mine by Jackson Steele, who has purchased them.

SAN BERNARDINO COUNTY.

J. C. Littlepage and William Van Slack have returned to San Bernardino from their

mine in Morengo district, where they have been doing some work. They intend to put in a five stamp mill in September.

A number of miners came down to San Bernardino from the Rose mine last week. They report great activity around the mines, and the discovery of a good body of ore at the seventh level, which averages \$30. The mill is not running on account of the scarcity of water, but workmen are now engaged in boring a 200-foot well in search of a good supply.

TUOLUMNE COUNTY.

The Brewer & Adams.

One of the greatest strikes the county has seen in a long time was made the first of the week in this mine, some of the ore extracted showing a value of \$15,000 per ton. The property is situated on the west side of Turnback Creek, and is an extension of the Pine-nut.

COLORADO.

Idaho Springs.

The Gold Medal mine, on the east of Seaton mountain, is running a cross-cut tunnel from the gulch some 600 feet below the main shaft. This tunnel is now in ten feet, and will be driven continuously for the eighty feet which are between the breast and the Gold Medal vein. As soon as the vein is reached it will be drifted on for 1,800 feet until a connection is made with the shaft. This property has produced some remarkably high-grade gold ore and can be relied on to live up to its reputation in the future. Mr. Emigh is the superintendent.

E. P. Blaisdell and Charley Corkett are sinking surface shaft on the Pride of Cascade lode, Ute creek, and are obtaining at grass roots quartz liberally sprinkled with chlorides, carbonates, sulphurets and some live mineral. The indications are flattering for an old-time Ute creek surface pocket and Blaisdell feels quite elated.

Crystal Items.

Seven men are at work at the Burke on Mineral Point, Gunnison county, getting the new tunnel under way in good shape. Work will be carried forward vigorously, and probably a contract will be let on the tunnel to drive it to cut the ore.

Two men have been added to the Inez force and we trust it will only be a few days until the force in this property is doubled. The present showing in the Inez is such as to lead one to expect good things to result from a comparatively small amount of development work.

Leadville Notes.

The Preston Mining and Milling Company, operating a large territory on Long and Derry hills, are about to push operations with three shafts. Ore has already been opened up which samples thirty ounces silver, 15 per cent lead and moderate values in gold. Mr. Darlington, of Kansas City, a heavy owner in the enterprise, visited the mine recently and seemed to be well pleased with the outlook.

The present lessees of the Nisi Prius Consolidated Mining Company's mines, in addition to the extensive work being done on the Hall shaft, are preparing to take the water out of the Crown Point shaft so as to get at sev-

eral small streaks of very high grade ore left when their property was formerly worked. The profits from the Carbonate workings will enable the operators to unwater the Crown Point shaft.

IDAHO.

The rolls for the Black Cloud concentrator, near Wallace, Idaho, arrived last week, and were at once taken up to the mill and placed in position. This places the mill in order for active operation and work was started on August 1st.

W. C. Squires, Talcott and E. D. Squires are the discoverers of a very promising mining claim in Lawyers' canyon, in the deep gorge about five miles from Nez Pierce City. The ore assays 83 ounces silver and 11.10 in gold. Total, \$227.60.

W. R. Mix and John P. Mix, of Moscow, will leave for Florence to continue development work on the Red Bird and Double Standard mines in that camp. W. R. Mix, who is superintendent of the company now developing the Red Bird under bond, spent the past winter sinking a shaft on the property. He also crosscut 100 feet on the ledge which at a depth of 130 feet is two and one-half feet wide. During the present summer several hundred tons of ore from this shaft will be milled.

MICHIGAN.

The Quincy Mining Co. has declared a dividend of \$3.50 per share, payable August 10, to stockholders of record on July 22. The last dividend paid was \$3 per share, in February, 1898. The amount of the present dividend is \$350,000, and it will bring the total amount paid in dividends by the company up to \$10,120,000.

The Wolverine company last week bought eighty acres of land directly west of the mine owned jointly by the Shelden, Douglas and Wolverine companies. The Kearsarge lode dips into the land and its possession will enable the Wolverine to mine to a depth of 5,000 feet. The price paid was \$130,000.

MINNESOTA.

The hearing over the reduction of iron ore freights from the Minnesota ranges to the lake ports has been in progress for a week, and so far the railroads have been ahead, except that the complainants have been able to show that the companies are making a great profit on the present rates. The hearing will continue two weeks longer.—*Engineering and Mining Journal*.

Wright-Davis Mining Company.

This company, with general offices at Saginaw, Michigan, and operations in Minnesota, filed articles of association in Saginaw recently. The capital stock of \$750,000 is held by the following people: A. W. Wright, C. H. Davis, W. T. Knowlton, G. M. Stark, E. P. Stone and A. Boutelle, all of Saginaw; J. F. Killorin, Duluth; Russell & Vincent, Minneapolis; and George F. Reynolds, Cheboygan, Mich.

MISSOURI.

Thos. Conner, John F. Wise and Joe Aldrich have purchased 40 acres of land near

Central City of Mrs. Barnes, for \$4,000. The tract adjoins the Missouri Central company's lease on the northwest. The land was purchased for its mineral value.

Bonshe & Company have leased the old Hickox farm south of Shoal creek and east of Redding's flour mill, and are taking out big chunks of lead ore from a drift six feet from the surface. Two men working two days took out 5,000 lbs. of lead ore.

On the Crown Point lease the Little Joe mine at Duenweg, is producing 20,000 lbs. of lead weekly with two men in the ground.

MONTANA.

The Old Glory mine, now in operation on a lease by J. Benton Leggat, is again on the list of producers. Mr. Leggat has made one of a series of shipments of ore to the Colorado smelter. Ore is being taken from a good-sized shoot at the 700 foot level and the returns show about 10 per cent. copper, 25 ounces in silver and some gold.

The southern portion of the mill at the Granite Bimetallic Consolidated Company's works, consisting of fifty stamps, has been started and is now running satisfactorily. The northern part of the mill has been shut down and is receiving a thorough overhauling. During the long shut-down the timbers and bolts have become loosened and it was necessary to replace a good many by new material, put in new foundations for the mortars in several places and make other repairs before it will be in first class running order.

The Blacktail district is 30 miles south of Libby creek. The ore is free milling. The formation is slate with occasional porphyry. Anaconda men own the Bell group, upon which the principal development consists of a main tunnel 100 feet, two tunnels 50 feet each and four shorter ones. These show the lead from six inches to six feet wide. It will probably average two feet. The Lucky Boy lies across the apex of the ridge and on Bramlet Creek slope and adjoining is the Lake claim, lying across the head of the creek. The former has a 50-foot tunnel. The Lake has one tunnel 25 feet, one 30 feet and a shaft 25 feet with a drift 25 feet long from the bottom.—*Helena Independent*.

NEVADA.

Nevada Mine Sale Suit.

Suit has been brought in the Utah United States court against Philo T. Farnsworth of Salt Lake City for the recovery of \$110,751 alleged to have been withheld through fraudulent misrepresentations as the price paid for mining and other property in Ione, Nye county, purchased for a Nevada company.

There were two transactions alleged as fraudulent in the complaint. The first alleges that the company furnished Farnsworth \$60,000 to purchase a stock of merchandise and other property at Ione for which he paid less than \$20,000. The second charge is that defendant was intrusted with \$130,000 to purchase the Ione Gold Mining Company's property for which he paid only \$80,000, withholding the balance of the money advanced in both transactions.

The Nevada company, or rather its board of directors, also operate the Nevada Central railway, which runs from Battle Mountain to Austin. The company's mining property is principally situated in the Austin mining district in Lander county.

NEW MEXICO.

The *Herald* of Bland, New Mexico, published the following description of the Cochiti cyanide plant:

The application of the cyanide process to the various ores found in the Cochiti district has been a difficult problem to solve, and the development of a suitable process is all that is required to make this one of the most important gold camps in the country because the immensity of the ore bodies has already been demonstrated. This the Cochiti Gold Mining Co.'s plant will unquestionably do. It is one of the most complete reduction works in America, and in the west is only equalled in completeness by the Golden Gate cyanide plant at Mercur, Utah.

Part of the mill has already begun operations and by the 10th of August the big plant will be running full blast.

The mill consists of steel frame and steel sheeted structures of a combined size of 350 x 75 feet; a hoist house and gallows frame; a leaching house 180x75 feet, containing five steel solution tanks 12x8 feet, 12 steel leaching tanks, 26x8 feet, eight precipitating tanks 15x8 feet, troughs and pumps for returning the cyanide solution to the tanks above; two additional rooms, consisting of an assaying room 30x25 feet and a department 90x30 feet to contain laundries and batteries; a furnace and boiler room 40x25 feet, containing two furnaces and boilers of a capacity of 100 horse power each; and engine room, 40x50 feet, containing machine shop, Ingersoll-Sargeant air compressor engine for operating drills in the mine, General Electric Co.'s dynamo with a capacity of 15, and a magnificent Corless engine made by the Edwd. P. Allis Co., with a horsepower of 160; a crusher and dryer house, 100x75 feet, containing two large ore bins of a capacity of 100 tons each, two crushers, eight roll feeders, two large furnace and rotary dryers, elevators, eight pulp rolls operating over two steel pulp bins of a capacity of 100 tons each. The two mill buildings, partly divided, are monstrous structures of steel with large girders and roof trusses gracefully light but strong. The mill is admirable adapted for the purpose, being most conveniently arranged, well lighted and ventilated, and is an excellent example of the great superiority of steel over wood for plants of this character. It is as near fire-proof as it is possible to build any structure. Besides being entirely of steel and masonry, it is lined throughout with asbestos sheeting. It sets in a cut out of solid rock, towering above the rear side, a face of rock some 40 feet high.

OREGON.

Mines of Cracker Creek.

It is stated that of the many prominent mining districts of Eastern Oregon, Cracker creek may be classed among the first. The North Pole, Columbia and E. & E. have given Cracker Creek wide fame, and now comes the Golconda, which promises even better than the older mines. The Golconda is off the market, and is in the hands of people who have money to develop it without taking out a pound of ore. Enough is known to safely assert that an ore body of unusual richness and extent has been opened up and that rush orders have been given, and men put to work to further develop the property and to put in a big mill, which it is asserted can be kept busy for an indefinite time on ore already uncovered.

The E. & E. is working about sixty men

in the mine, and one-third of that number in their 20-stamp mill. The mill is handling 80 tons of ore daily, reducing to concentrates at a ratio of 25 to 1.—*Oregon Mining Journal*.

SOUTH DAKOTA.

D. C. Boley has let a contract to run a 50-foot tunnel about 25 yards from the shaft in Blacktail gulch, to D. H. McDonald and N. S. Peck.

The Keystone mill is being enlarged at present by the addition of 20 more stamps. Ed. Major, who built the Kildonan, and the St. Elmo, is superintending the work.

Chas. H. Lockie and Chas. Graham have purchased the lease formerly held by Thomas Adams on part of the Dakota Maid. The new owners intend to put a force of men at work sinking on both shafts.

Work is progressing as rapidly as possible on the chlorination works at Rapid City. The boilers were tested last week and the familiar sound of the old steam whistle brought a hearty cheer from the citizens of Rapid. Col. Day thinks everything will be in readiness for the reception of ore in three or four weeks.—*Black Hills Mining Review*.

UTAH.

The *Mining Reporter*, of Denver, has a very interesting article from one of its correspondents, in the La Sal mountains of Utah, from which we take the following extracts:—

"There is probably no new mining section in the western country of which there is so little known as the La Sal district, bordering on the western part of Colorado. Many contend that this promising section of country belongs in a greater part to Utah, but as yet no Utah men have shown a disposition to develop its various resources. In fact, there are no class of miners and prospectors developing and exploring this section but Colorado men.

The La Sal range proper is divided into what is known as the north and south divisions, separated by a low pass called Geyser pass.

Very little prospecting has been done in the south division, yet one of the biggest copper mines of the country is being developed there, the Big Indian property, recently purchased by Ed. Loose and others, of Provo and Salt Lake, from Capt. May and S. N. King, two well known San Juan, Colorado, mining men. There is a big country between Geyser Pass and the south end of the mountain, and from reports, some rich gold and copper veins are being discovered."

WASHINGTON.

Colville Reservation.

Some good reports continue to come in from Sheridan Camp, although not much development work is going on at present. Snyder & Carter's claims show up well, as do several others along the main ledge. The high assays come from narrow seams in the ledge matter, but it is believed that these rather meagre veins will widen as depth is reached. All those having prospects at Sheridan are confident of finding rich and large deposits at lower depths. The latest assay from there shows \$65 in gold and 920 ounces in silver.—*Miner and Electrician*.

FOREIGN MINING NEWS

BRITISH COLUMBIA.

"Since the Canadian Pacific bought the Trail smelter, it has been overhauling and enlarging it. It is being changed from a two to a five-furnace plant, so that it will handle from 750 to 1,000 tons every twenty-four hours, and will treat not only sulphide but silver-lead ores from the Slocan. The entire plant will be run by electricity, for they are now equipping it with motors. They have a plant of 400-horse power in the town, and are bringing in wires from the Kootenay Power Company's plant at Bonington Falls on the Kootenay River, which will develop 10,000 horse power, and will supply the whole district. The company has reduced the cost of freight from Rossland to Trail, and of treatment at the smelter from \$11 to \$7.50 a ton, and will make lots of mines pay which would not pay at the old rates. Some of these have begun development, and will eventually ship ore. The War Eagle is putting in an electric plant and will be the first to use that power.

A Good Showing.

The mines in Rossland are turning out ore in a manner which promises to fulfill even the most sanguine prediction as to the future of the great camp. The War Eagle is now sending out about 1200 tons per week, and when machinery, now in process of installation, is in working order, the output will be materially increased. The Center Star will join the ranks of the steady shippers as soon as the new electrical hoist is in place. The Iron Mask is shipping regularly as is the Monto Christo. The Le Roi is about to increase from 200 tons per day, and it is stated that the Columbia-Kootenay will soon join in increasing the already great stream of ore constantly flowing from this camp. All together this is a showing of which Rossland may well feel proud.—*B. C. Mining Critic*.

LOWER CALIFORNIA.

The Trinidad Mining Company, owning the Trinidad group in the Jacalitos district, which includes the Piedad mine, contemplates the extensive development of its property and will probably commence work within a fortnight. All these evidences of renewed activity, taken in connection with the two new prospecting mills for the Socorro district to the south, and a marked revival of the industry at Calmali, give Peninsula mining a more promising outlook than it has enjoyed for a couple of years past.

MEXICO.

Zacatecas.

The San Cristobal Gold Mining Company, a New York concern, has recently put in a large thirty-stamp mill, and it is reported that the Richmond and Zacatecas Gold Mining Company will soon put in at their Australia mine and Anexas a large and modern milling plant. The mine is situated within 2,000 yards of the town of Zacatecas, and it has a large and well-defined vein of fairly good ore. Owing to one cause or another, however, the mine has never been handled to advantage, but the shareholders are now beginning to hope for better things.

Chihuahua.

The Reina mine near Cusiuhiriac, is producing a large amount of rich ore. It has 4000 miners at work. In the last year it has produced \$500,000 silver, has also an equal amount in ore on the dump and over a million more in sight. The Santa Elena, in the same district, ships from 40 to 75 cars of ore daily to the Aguascalientes smelters. Many new mines are being denounced in that part of the state and some of them promise to be very rich.—*Chihuahua Enterprise*.

PERSONAL NEWS ITEMS

P. LAWRENCE of Butte, Montana, is in Los Angeles for his health, having recovered from the third attack of pneumonia.

JOHN BECK of the Bullion-Beck, devoted several days to a visit in Colorado last week.

R. S. SPENCER, chief owner of Humming Bird, Paris, Idaho, is in Salt Lake City, Utah.

A. C. LIPPENCOTT, of Boise, Idaho, was in Salt Lake City last week for several days.

M. W. GIBBONS, of the Kasser G. M. Co., has returned to Globe, Arizona, from California.

T. R. JONES has returned to Utah from a visit among the smelter men of the east.

CHAS. H. KARLSRUH, president, and A. Vos, secretary-treasurer Phoenix G. M. Co., Nevada City, California, have returned to their homes in the east.

W. H. ALLBRIGHT of Boston, has been visiting Utah, where he has several mining interests.

P. KERRIN of the Comstock at Virginia, Nevada, is at Grass Valley, Cal., examining the Allison Ranch mine.

S. B. MILNER has been elected manager of the Dexter Mining Co., at Tuscarora, Nevada.

GEO. CROCKER, of the Southern Pacific Co., is putting \$100,000 into the development of the Alicemine Idaho Springs, Colo.

A. THIES of the Haile Mine in South Carolina, visited New York last week on his way home from a short vacation trip.

R. NICHOLS, formerly superintendent of the Sutro tunnel and now a mine manager at Coolgarde, West-Australia, is in Virginia City, Nev.

MESSERS. B. H. PAYNE, C. C. MCCARTHY, WILLIAM BRILL, F. A. DAGGE and COL. CHAS. E. WARE recently inspected some mineral land near Joplin, Mo., which they propose to develop.

O. S. BUCKNER, who went to Fort Mohave, Ariz., a few weeks ago to become superintendent of Sheep Trail mine, is at home in San Francisco, Cal., in ill health.

W. B. RICHARDSON, mining engineer, with La Dura Mining & Milling Co., is in San Francisco, Cal. The company's mines are in Sonora, Mexico, about 100 miles from Ortiz, on the Sonora railroad.

J. C. BOYD of the Gaston M. Co., at Gaston, Col., is on his way to Tasmania via San Francisco, whither he goes on mining business for his company.

CHAS. H. MERRILL, who has been engaged for two years past in mining explorations in Michoacan, Mexico, was in New York last week. He purposes spending a month in the east, after which he will go to South America on professional business.

W. H. HARDINGE, the mining engineer of Denver, Colo., is again in our midst. Mr. HARDINGE has made several visits to Southern California in the last few years.

THOR. F. VAN WAGENEN, M. E., has kindly consented to allow us the use of his article published in the *School of Mines Quarterly* on the System of the Location of Mining Districts. Mr. VAN WAGENEN is a thorough metallurgist and is also an authority on hydraulic mining, being the author of *The Manual of Hydraulic Mining* for the practical miner. His article on the Location of Mining Districts is not a new theory by any means, having received the consideration of such eminent professional men as Dr. R. W. RAYMOND, CLARENCE KING, J. P. KEMP and others. The article above referred to will be published in our issue of September 1st, and those interested in the geology of the country will do well to secure a copy of the JOURNAL and read it!

THE MARKETS.

NEW YORK, Aug. 6, 1898

The following are the Silver, Copper and Lead quotations for the last two weeks:

	SILVER.	COPPER.	LEAD.
July 1	103 1/2	11 60	13 02 1/2
15	103 1/2	11 50	13 02 1/2
29	103 1/2	11 50	13 02 1/2
Aug. 1	103 1/2	11 50	13 02 1/2
15	103 1/2	11 50	13 02 1/2
29	103 1/2	11 50	13 02 1/2
Aug. 6	103 1/2	11 50	13 02 1/2

Spain, it is understood, is not now on the market for silver, and the price has declined to about the Indian basis. At the close the market is reported as a limited one.

The United States Assay Office in New York reports the total receipts of silver at 174,000 oz. for the two weeks ending Aug. 6th.

COPPER

The market is steady at the decline, but very little is doing. Buyers have been trying to obtain further concessions which producers emphatically decline to grant.

For electrolytic copper we have to reduce to 11.37 1/2 @ 11.50c. for cakes, wire bars or ingots, and 11.15 @ 11.25c. for cathodes. Casting copper is nominal at 11 1/2c.

LEAD

The opening was rather firm, but subsequently more lead came out both from first and second hands, which had somewhat depressing influence on prices and

the market eased off to 3.85c. St. Louis, and 3.95c. New York.

SILVER

Producers have been few sellers, probably in consequence of ore prices having been more reasonable during the week. Fortunately, there was a fair consumptive demand and prices are in consequence steady at 4.35 @ 4.37 1/2c., New York.

ANTIMONY

Antimony continues strong, and we quote Cookson's 9 1/2c.; Hallett's, U. S. Star and Japanese, 9 1/2c.

NICKEL

Business still continues on unchanged lines and no alteration in prices can be reported. We quote for New York ton lots 33 1/2c. and 36c. per lb. and for smaller orders 35 1/2c. and 38c.

TIN

Early in the week prices had eased off somewhat, but at the close no new concessions are obtainable from importers, and we quote 15 1/2 @ 15 3/4c. for July-August shipment and 15 3/4 @ 16 1/4c. for later deliveries.

PLATINUM

Prices are now quoted at \$15 and \$16 per oz., New York. The London quotations are 58 @ 60s per oz. Supplies are not large and prices are firm. For chemical ware, best hammered metal, Messrs. Eimer & Amend of New York furnish the following quotations: In lots of 250 grams or more, 56c. per gram; in lots of 100 grams or more, 57c. per gram; less than 100 grams, 58c. per gram; unmanufactured platinum will be supplied in same quantities at 2c. less per gram.

POTASSIUM CYANIDE

Purified, 98 @ 99 per cent., in cases of 12 lb. at 32c. per lb. in 5, 10, 25 and 50 lb. tins at an advance

QUICKSILVER

The New York price has been again reduced 50c., and is now \$42 per flask, or \$1 lower than three weeks ago. The London quotation is unchanged at £7 12s. 6d., with the same price named from second hands.

POWDER

F. o. b., San Francisco: No. 1, 70 per cent. nitro-glycerine per lb. in carload lots, 15 1/4c. less than one ton, 17 1/4c. No. 1* 60 per cent., carload lots, 13 1/2c. less than one ton, 15 1/2c. No. 1** 50 per cent., carload lots, 11 1/2c. less than one ton, 13 1/2c. No. 2, 40 per cent., carload lots, 10c. less than one ton, 12c. No. 2*, 35 per cent., carload lots, 9 1/2c. less than one ton, 11 1/2c. No. 2** 30 per cent., carload lots, 9c. less than one ton, 11c. Black blasting powder in carload lots, minimum car, 728 kegs, \$1.50 per keg; less car lots, \$2 per keg

COKE

The coke market has been quite dull the past week, and entirely without features of interest

IN CAR LOTS, ST. LOUIS

Connellsville fly coke 72-hr. fly \$1.85
New River... \$4.00 Pocahontas... 3.90
Crushed... 4.85
Gas works coke, lump, per bushel... 10

BORAX

The San Francisco market in Borax is firm with a good demand.

The market is quoted as follows:

Refined, in carload lots, in barrels... 7 1/2
Refined, in carload lots in sacks... 7
Powdered, in car lots... 6 1/2
Concentrated, in car lots... 6 1/2

THE MINOR METALS.

Quotations are given below for New York delivery:

Aluminum:
No. 1, 98 per cent. ingots, per lb. 1.04 @
No. 2, 90 " " " " 1.00 @ 1.04
Rolled sheets, per lb. 1.00 @ 1.04

Aluminum.—Nickel per lb. 1.00 @ 1.04
Bismuth, per lb. 1.00 @ 1.04
Phosphorus, per lb. 1.00 @ 1.04
Tungsten, per lb. 1.00 @ 1.04
Perovskite, 50 per cent 1.00 @ 1.04

Variations in price depend chiefly on the size of the order

CHEMICALS

There has been no material change in demand for heavy goods.

Quotations generally are as follows:

CAUSTIC SODA

Quotations for Caustic soda domestic high test are \$1.40 @ 1.50 per hundred lbs

ALKALI

Domestic, 58 per cent., 50c. @ 55c., foreign 55c. @ 60c. from dock as to style of package

CARBONATED SODA ASH

58 per cent., 90c. and 95c. per 100 lbs. basis 48 per cent.

BI-CARBONATE OF SODA

English, \$2.12 1/2 @ \$2.25 per 100 lb. American, bulk \$1.25 and \$1.50 per 100 lbs. according to brand.

SAL SODA

For domestic, 50c. per 100 lb., less usual discounts; English, 62 1/2c. and 65c. Concentrated sal-soda, \$1.60 @ \$1.65 per 100 lbs

CHLORATE OF POTASH

Chlorate of potash is quoted at \$9.25 and \$9.50 per 100 lbs.

CHLORIDE OF LIME

English prime brands \$1.50 @ \$1.60, Ordinary, \$1.70 @ \$1.80; Continental, \$1.40 @ \$1.50 per 100 lbs.

Acids.

The market for the following acids lacks interest; has practically been at a standstill, through prices are pretty steady.

LEHIGH UNIVERSITY

South Bethlehem, Pa.

THOMAS MESSINGER DROWN, LL.D., Pres.


Courses in Civil, Mechanical, Electrical and Mining Engineering, Metallurgy and Chemistry. Also Classical and Literary Courses. For further information, and for Registers address, The Secretary of Lehigh University, South Bethlehem, Pa.

SAVE MONEY! FUEL COSTS MONEY



Protect your pipes and boilers with Wm. Berkfield's Fossil fuel composition, packed in sacks, easy to transport anywhere. Send for facts and figures.

FOSSEL FUEL CO.
2 Cedar Street, New York



LARGEST GASOLINE PUMPING PLANT IN THE WORLD

The illustration shows the gigantic pumping plant recently built by the Hercules Gas Engine Works at the Packer Ranch, Colusa Co. 80 h. p. Hercules Engine, pumping 7200 gallons a minute, 27 feet high. Burns Gasoline or Distillate oil. Cheapest power known. Gas, Gasoline and Oil Engines, 2 to 200 h. p. Send for Catalogue. HERCULES GAS ENGINE WORKS, 210 Bay St., San Francisco.


Hoskins' Patent Hydro-Carbon

Blow-Pipe and Assay Furnaces

No dust. No ashes. Cheap, effective, economical, portable and automatic. Send for Price-list to

WM. HOSKINS,

81 South Clark St., Room 57
CHICAGO, ILL.



W. T. SMITH

"Photo Brown 313"

JAMES IRVING

SMITH & IRVING,

(FORMERLY, W. T. SMITH & CO.)

Gold Refiners and Assayers.

Our silver amalgam for replating copper plates is being extensively used by millmen. It avoids the necessity of sending plates long distances to be replated. For sale in small quantities, 50c per ounce, a reduction being made on all orders over 20 ounces. Experience proves our silver amalgam will catch more gold than when the copper is electroplated. Our Mr. Smith owned and operated Smelting, Refining and Chemical works in Providence, R. I., for over 20 years.

128 N. Main Street

MISSION THE JOURNAL

Los Angeles, Cal.

BELTING


Leather, *
Cotton,
Rawhide, etc.

TELEPHONE 562
ALSO —
Lace Leather

L. P. DEGEN, Manuf'r

Agent for Rubber Belting, Hose and Packing.

105 and 107 Mission Street, San Francisco, Cal.



PERFORATED SCREENS

Steel Plate, Copper and Bronze

For all uses. Send for Catalogue

A. J. BECKLEY & CO.

Works, Garwood, N. J.

New York Office, 123 Liberty Street.



J. H. MASTERS,

Manufacturer of and Dealer in

Ore Sacks, Tents & Camp

Furnishings

217 Commercial St.,
LOS ANGELES, CAL.

* ADVERTISE IN THE JOURNAL *

Quotations are per 100 lb from New York and vicinity as follows: Acetic acid, commercial, No. 8, \$1.40@1.50; muriatic acid, 18°, \$1.10@1.15; 20°, \$1.20@1.27½; 22°, \$1.35@1.42, according to quantity and brand. Nitric acid 36° \$1.50@1.75, 38° \$1.75@1.90, 40° \$1.80@1.87½, 42° \$1.62½@1.65, 44° \$1.60@1.65, 46° \$1.60@1.65. Oxalic acid \$6.50@6.75. Mixed acid, according to mixture. Sulphuric acid, 46°, \$1.10 for drums and \$1.15@1.75 for carboys, Chamber acid 50°, in jobbing way, \$11.50@12 per ton f. o. b. factory. Blue vitriol \$3.50@3.62½ for extra grades and \$3.37½ for ordinary.

BRIMSTONE

We have again to record a quiet market, with prices about 50c. a ton lower than last week. Best unmined stones can be had for \$21@21.50 a ton while thirds are sold at \$19@19.50.

MURIATE OF POTASH.

We quote per 100 lbs. on basis of 80 per cent., as follows: New York and Boston, \$1.78 for 80@85 per cent., and \$1.81c for 95 per cent.; Norfolk and Philadelphia, \$1.78½ for 80@85 per cent., and \$1.79½ for 95 per cent.; Charleston, Savannah, Wilmington, N. C. and New Orleans, \$1.78½ for 80@85 per cent., and \$1.81½ for 95 per cent. All for lots of 50 tons and upward.

KALIN.

Invoice weights as taken at port of shipment per ton of 2,240 lbs. testing 12.4 per cent. actual potash, equivalent to 23 per cent. sulphate of potash, \$8.55 @ \$8.80 for New York and Boston; \$8.90 @ \$9.15 for Norfolk, and Philadelphia; and \$9.05@9.30 for Charleston. Sa-

vannah, Wilmington, N. C., and New Orleans.

NITRATE OF SODA.

Spot nitrate is in ample supply and buyers have the upper hand for the present. We have again to quote a little lower price, \$1.50@1.55 per 100 lbs. for spot. The same figures are quoted for futures, in view of the quantities known to be afloat for New York.

FINANCIAL NOTES.

The statement of the United States Treasury, on Thursday, July 28th, shows balances in excess of outstanding certificates as below, comparison being made with the statement for the corresponding date last week.

	July 28	Changes.
Gold.....	\$1,172,535 1	\$2,266,297
Silver.....	13,742,192 1	715,036
Legal Tenders.....	4,068,781 1	1,615,487
Treasury Notes, etc.	4,095,105 1	41,635

Totals..... \$13,180,613 1 \$5,638,455

Treasury deposits with national banks amounted to \$57,627,771, an increase of \$97,771 during this week.

Average Monthly Prices of Silver.

In New York per ounce Troy, from January 1st, 1898, and for the years 1897 and 1898:

Month.....	1898	1897	1896
	Cents.		Cents.
January.....	56.77	56.79	67.13
February.....	56.97	56.67	67.37
March.....	56.90	56.86	68.40
April.....	56.92	56.85	67.92
May.....	56.88	56.13	67.78
June.....	58.41	59.10	68.69
July.....	59.46	59.61	68.75
August.....	59.41	59.34	67.31
September.....	55.57	55.57	65.68
October.....	57.91	56.85	66.85
November.....	58.01	57.91	64.93
December.....	58.01	58.01	65.21
Year.....	56.79	56.79	67.73

Gold and Silver Exports and Imports.

At all United States ports, June, 1898, and years from January 1st, 1898 and 1897.

	Coin and Bullion Exp.	Imp.	In Ores Exp.	Imp.
Gold.....	\$ 125,520	\$ 1,084,274	\$ 22,411	\$11,735
June.....	6,045,000	99,216,254	72,411	7,539,614
1898.....	12,000,712	1,211,240	91,155	7,539,614
Silver.....	3,106,000	7,677,855	112,000	2,281,045
June.....	21,392,000	3,302,110	112,000	9,127,327
1897.....	32,503,000	4,419,290	269,150	1,500,000

This statement includes the exports and imports at all United States ports, the figures being furnished by the Bureau of Statistics of the Treasury Department.

Shipments of silver from London to the East for the year up to July 11th are reported by Messrs. Pixley & Abell's circular as below:

	1897	1898	Changes.
India.....	\$2,847,700	\$2,987,440	\$139,740
China.....	109,942	354,140	244,198
The Straits.....	106,405	150,792	44,387
Totals.....	\$2,964,047	\$3,492,372	\$528,325

The statement of the Bureau of Statistics for June puts the exports for that month at \$94,808,263, which is still a very high figure, while imports were \$51,267,591. For the fiscal year ending June 30th the statement is as follows:

	1897.	1898.
Exports.....	\$1,050,933,556	\$1,231,311,868
Imports.....	764,739,412	616,052,814
Excess, exports.....	\$286,194,144	\$615,259,054
Add excess of exports, silver.....		31,411,411
Total.....		\$646,670,465
Deduct excess of imports, gold.....		164,985,293
Net apparent balance.....		\$481,685,172

POSITIONS WANTED

Advertisements of this class containing not more than five lines will be inserted for not exceeding three months in any year, free of charge, to all paid-up annual subscribers. Other than above \$1.00 per month will be charged. Advertisements not accepted for less than one month.

WANTED, by a young experienced man, position as quartz mill man, one who can keep mill running. Address, A. E. CHARLESWORTH, LOCKFORD, CAL.

WANTED by a young man, a position as Assayer, etc.; experienced, competent and has a good knowledge of all metallurgical operations. Good references. Address, T. K. JOURNAL OFFICE, STIMSON BLOCK, Los Angeles, Cal.

WANTED—Situation by Millman and Assayer. Wages reasonable. Good references. Address "H" JOURNAL OFFICE.

EXPERIENCED Assayer and Cyanide operator desires engagement. The successful and economical treatment of siliceous ore or tailings by cyanide a specialty. Address W. V. WATSON, Ely, White Pine Co., Nev.

AN INDEPENDENT Chemist and Millman, thoroughly understands Milling, Chlorination and Cyanide Processes. Twelve years experience in Montana and Colorado, now open to an engagement. Moderate salary. Address "Chemist" JOURNAL OFFICE, Los Angeles, Cal.

FOR SALE!


I HAVE some good gold mining properties for sale at reasonable prices, some developed and some real good properties at Ward, Eldora, Gold Hill, Jamestown, Magnolia, Caribon and Sugar Loaf. Write stating what you want or call on me. JAMES M. NORTH, Former County Judge, BOULDER, COLO.



Assayers and Laboratory

Glassware and Porcelain Ware, Magnifying Glasses, Thermometers, Altitude Barometers, Compasses, and Microscopes, Wholesale and Retail. Correspondence Solicited. Prices quoted on application.

Pacific Optical Company, 245 S. Spring St., Los Angeles, Cal.



Engines Boilers Saw Mills

Write for Catalogue and Prices. RUSSELL & CO. PORTLAND, OREGON.

FOR SALE!

One 35"x34" Water Jacket Furnace, Boiler, Engine Blower, Rock Breaker, Scales, Shafting, Pulleys, Belting, Tools and all fittings and fixtures complete and new, built by Fraser & Chalmers; also one 10x40 Hamilton Corliss Engine; one 10x10 double Cylinder Hoisting Engine. Will be delivered f. o. b.

W. E. DAME, CERRILLOS, NEW MEXICO

ASSAYER and CHEMIST

Mark samples plainly, advise by letter of full details, with charges enclosed. Postage on ore one cent per ounce.

C. H. VOLL, SEATTLE, WASHINGTON

34 Boxwell Bldg.

The Baker & Adamson Chemical Co.

MANUFACTURERS OF

Strictly Chemically Pure Acids and Chemicals and Ashless Filter Papers

EASTON, PENNSYLVANIA

ADOLF FRESE ENGINEERING INSTRUMENTS

Barometers, Thermometers, Field Glasses, Microscopes and Accessories. Repairing Promptly Done.

126 S. Spring St., LOS ANGELES, CAL.

Oilless Bearings,



For

Rope Tramways, HOISTING Engines, Tackle Blocks, Cam Shafts in STAMP MILLS. A Practical BEARING that RUNS WITHOUT OIL

The Graphite Lubricating Company

BOUND BROOK, N.J.

Sulphuric Acid

FOUNDRY

Mining Machinery

Iron and Brass Castings of all kinds, Shoes and Dies, Pumps, Engines, Boilers, Stamp Mills, etc., etc. Machinists and Foundrymen.

Standard Iron Works, PHOENIX, . . . Arizona

A. F. JUDSON, E.M.

Geologist and Mining Engineer,

Mines Examined and Reported on. COLTON, CALIFORNIA

A. A. WARREN

ASSAYER AND ANALYTICAL CHEMIST

COLTON, CALIFORNIA

Manufactured by the Western Chemical Co. Denver, Col. For Chlorination Refining and other processes. Also Muriatic and Nitric Acids, Blue Vitriol, Copperas Refined Sulphate of Soda, Etc.

ASSAYERS AND CHEMISTS

WADE & WADE

Best and Oldest Establishment in Southern Cal.

115½ N. Main St., Los Angeles, Cal

Chas. P. Grimwood,

Mining Engineer and Metallurgist

Laboratory, 214 Pine Street,

SAN FRANCISCO, CAL.

MINING STOCK QUOTATIONS

BOSTON	
Aetna Cin	do, rights..... 55
Allouez	3 38 Gold Con..... 1 00
Anaconda	Humboldt..... 4 75
Arnold	16 85 Illinois Steel..... 60 00
Ash Bed	3 88 Lake Sup Iron..... —
Atlantic	28 00 Merced..... —
Baltic	17 88 New Idria Mfg..... 75
Bonanza	National..... —
Boston and C C	Old Dominion..... 28 00
Boston & Mont's 211 1/2	Oxaca..... 55 25
Butte & Boston	21 75 Parrott..... 22 00
Calumet & Hecla 1675 00	Pioneer..... 5 75
Catalpa	Quincy..... 113 1/2
Centennial	16 50 San Ysaabel..... 165 00
Dominion Coal	24 00 Tamarack..... 2 60
Dominion Prof	168 1/2 Tecumseh..... 2 60
Franklin	14 75 Wolverine..... 23 00

NEW YORK.

Alamo	03 1/2 Homestake..... 23 50
Alice	40 Iron Silver..... —
Annetta	45 Mexican..... 30
Best & Belcher	80 Mollie Gibson..... 19
Brumswick	05 Ontario..... 4 50
Bulwer	05 Ophir..... —
Crown Point	65 Pharmacian..... 10
Con. Cal. & Va	Plymouth..... —
Cripple Creek Con	08 1/2 Quicksilver..... 3 00
Deadwood	Quicksilver pfd..... 11 00
Favorite	11 25 Sierra Nevada..... 21
Fortuna	04 Standard..... 1 80
Golden Fleece	45 Union Con..... —
Gould & Curry	45 Yellow Jacket..... —
Hale & Norcross	—

SAN FRANCISCO.

Alpha	10 Exchange..... —
Alta Con	09 Gold & Curry..... 1 85
Andes	08 Hale & Norcross..... 1 85
Belcher	23 Justice..... 55
Best & Belcher	27 Mexican..... 21
Bodie	— Ophir..... 80
Bullion	10 Overman..... —
Challenge	28 Potomac..... 21
Chollar	16 Savage..... 67
Confidence	85 Sierra Nevada..... 10
Con. Cal. & Va	49 Union Con..... 11
Con. New York	— Utah..... 07
Crown Point	13 Yellow Jacket..... 30

COLORADO SPRINGS STOCKS

Alamo	02 Jack Pot..... 03 1/2
Anaconda	52 1/2 Lexington..... —
Argentum Juanita	26 Little..... 80
Bob Lee	— Magnet R..... 00 1/2
Credle & C Co	03 1/2 Marion..... 15
C C Consolidated	09 Minto..... 24 1/2
Dea Moines	— Mollie Gibson..... 74 1/2
Elkton Con	93 Moon A's Cr..... 01 1/2
El Paso	15 New Haven..... 05
Fanny R	— Pharmacist..... 99 1/2
Favorite	03 1/2 Pilgrim C..... 01 1/2
Fludley	— Portland..... 00 1/2
Franklin	— Pr Albert..... 00 1/2
Golden Crafter	00 1/2 Specimen..... 00 1/2
Golden Fleece	— Therese..... 00 1/2
Gold & Globe	00 1/2 Trichite..... 00 1/2
Hayden	00 1/2 Union Gold..... 00 1/2
Ing. Con	00 1/2 Work..... 00 1/2
Isabella	28 1/2 Work..... 00 1/2

SALT LAKE CITY

Alice	70 Lucky Bill..... —
Ajax	30 Mulvren..... —
Alliance	— Mammoth..... 1 87 1/2
Anchor	20 Maxwell..... 7 25
Buckeye	02 Mercur..... 10
Bull Back	5 50 Morgan..... 25 1/2
Cent. Bureau	32 Northern Light..... 3 00
Chloride Point	85 1/2 Omaha..... 27 1/2
Dalton	00 1/2 Ontario..... 3 00
Daly	70 Overland..... 03 1/2
Daly West	3 50 Richmond Ana..... 03 1/2
Dalton & Lark	06conda..... 03 1/2
Dexter	1 02 Itovar..... 45
Eagle	04 Sacramento..... 18 50
Kureka Hill	— Silver King..... 04
Four Aces	04 Sioux Con..... 08
Galea	42 Sunbeam..... 2 42 1/2
Gemini	— Swansea..... 1 18 1/2
Geyser-Marion	6 80 So Swansea..... 60
Grand Central	00 1/2 Utah..... 1 37 1/2
Homestake	00 1/2 Utah Con..... 57 1/2
Horn Silver	1 37 1/2 Young America..... 57 1/2
Little Pittsburg	01 1/2 Young America..... 57 1/2

ROSSLAND, BRITISH COLUMBIA.

Alberta	05 Josie Mac..... 18 1/2
B. C. Gold King	07 Josie..... 38
Beaver	10 Jumbo..... 75
Big Three	10 Knight Templar..... 05
Bluebird	07 Kootenay-London..... 10
Bruce	19 Le Roi..... 8 00
Butte	01 1/2 Lily May..... 18
Caladonia Con	05 1/2 Mabel..... 15
California	15 Mayflower..... 10
Camp Bird	05 Monita..... 18
Delia Colla	05 Monte Christo..... 05
Centre Star	— Morning Star..... 05
Colonna	24 Mugwump..... 03
Commander	18 Nest Egg..... 05
Deer Park	12 1/2 Northern Belle..... 09
Delia Colla	02 Noxely..... 10
Delaware	12 O. K..... 10
Eastern Star	20 Palo Alto..... 05
Enterprise	20 Phoenix..... 13 1/2
Eric	03 1/2 Poorman..... 15
Eureka Con	05 1/2 R. E. Lee..... 15
Evening Star	05 1/2 Red Eagle..... 09
Georgia	10 1/2 Red Mount View..... 05
Gertrude	10 1/2 Red Point..... 05
Golden Hope	15 Ross'd H'mest'ke..... 05
Gord Hope	02 1/2 Rossland, Red Mt..... 20
Grand Price	03 1/2 St. Elmo..... 05
Great Western	08 St. Paul..... 12 1/2
Hattie Brown	— Silver Bell..... 04
Helen	04 Silverline..... 09
High Ore	04 1/2 So Cross & W. Con..... 20
Imperial	10 Virginia..... 12
Iron Horse	20 War Eagle Con..... 10
Iron Mask	38 West Le Roi..... 10
I. X. L.	10 White Bear..... 11

DENVER STOCK REPORT.

Aetna	00 1/2 Keystone..... 01
Anaconda	51 Little..... 80
Arcadia	00 1/2 Moon A..... 78
Argentum Juanita	28 Mt Rosa..... 12 1/2
Beaumont	07 Old Gold..... 05 1/2
Bob Lee	00 1/2 Peoples..... 01 1/2
C C Con	08 1/2 Pilgrim C..... 00 1/2
Elkton	30 1/2 Pine Creek..... 00 1/2
El Paso G	05 1/2 Portland..... —
Enterprise	02 1/2 Prince Albert..... —
Garfield Group	05 Republic..... 02 1/2
Geo. Washington	00 1/2 Sacramento..... 02 1/2
Golden Eagle	34 Specimen..... 03
Gold Con	38 Tamarack..... 00 1/2
Gilpin & C Co	08 1/2 Union Gold..... 10 1/2
Gilpin Four	00 1/2 Virginia M..... 03 1/2

Iron Clad	02 1/2 West of Fortune..... 00 1/2
Knob Hill	23 1/2 West..... 02 1/2
Jack Pot	02 1/2

MEXICO

Name of Company	State	Price
Alamita	Hidalgo	5
Amistad y Concordia	"	24
Angelus	Guanajuato	349
Arceval y Anexa	Hidalgo	210
Asustan y Anexa	Zacatecas	170
Barradon y Cabras	Durango	150
Bartolome de Medina	Hidalgo	100
Cabezon y An	Zacatecas	30
Candelaria de Pinos	"	150
Canzonay	Durango	150
Carmen	Hidalgo	400
Catellana y San Ram	Tepe	25
Cerro Colorado	Chihuahua	10
Cinco Senores y An	Guanajuato	480
Concepcion y Anexa	Quintana Roo	100
El Oro	Guanajuato	40
Epapayun y An	Mexico	1 300
Guadalupe	Guanajuato	180
Huautla	Santa Ana	100
Luz de Borda	Michoacan	100
Luz de Maravillas	Hidalgo	100
Pahellon	Zacatecas	100
Palma	"	100
Parloma de los Com	"	900
Real del Monte	Hidalgo	3
Refugio y Va	Durango	30
Restauradora	Hidalgo	270
San Francisco	"	12
S. Pad. Chalchihuites	"	925
San Rafael y Anexa	"	460
do. Free Stock	"	400
San Rafael del Oro	Hidalgo	70
San Maria de la Paz	S. Luis Potosi	650
Sirena	Durango	500
Soledad	Hidalgo	250
Sorpresas	"	40
Trinidad	Guanajuato	150
Union	Hidalgo	280
Uruapan	Puebla	100
Zonahuacan (gold)	Vera Cruz	100
Zona Min de Pozos	Guanajuato	15

Note—The above Mexican stocks are figured on the basis of Mexican silver

ORE TESTING

Complete mill for testing ore on practical scale by all processes to determine the best process adapted to treating any ore submitted. Processes in use investigated to overcome unnecessary losses, etc.

RICKETTS & BANKS.

Metallurgists & Chemists

No. 104 JOHN STREET,

NEW YORK CITY



Krogh Manufacturing Company

Successor to San Francisco Tool Co.'s Machine & P'f'g Dept.
MANUFACTURERS OF AND DEALERS IN

MINING AND PUMPING MACHINERY,

— COMPRISING —

Briggs' 2-Stamp Triple-Discharge Quartz Mill, of latest improved pattern, Rock Breakers, Ore Feeders, Concentrators, Engines and Boilers, Hoisting Rigs to be operated by Horse, Steam Power or any other motor; Ore Cars and Ore Buckets, Corbels and Jack-heads, Pumps, Triple-Acting Pumps, Centrifugal Sand and Gravel Pumps, Wooden Tanks and Pumps for the Cyanide Process, Pipe and Gate Valves, Link Chain Elevators for elevating and conveying all kinds of material. Estimates as to cost of machinery and its erection furnished upon application. Write for Catalogue and Prices.

OFFICE AND WORKS AT

51 Beale St. and 9 to 17 Stevenson St.,

San Francisco, Cal.

Assay Office *

LEW E AUBURY

115 W. First St.,

Opp. Nat'l House

Los Angeles



BRANCH OFFICES:

1428 E St.,

SAN DIEGO, CAL.

* * *

523 1st AVENUE,

SPOKANE, WASH.

The Southern California Lumber Co.,

Stimson Bldg., Los Angeles, Cal.,


Chas. Wier Manager, sells

LUMBER

At Wholesale Prices

Mining Timbers a Specialty

Write for Prices



AIR COMPRESSOR

THE INGERSOLL-SERGEANT DRILL CO.,

Rock Drills

AND

Air Compressors

MODERN, DURABLE AND
GUARANTEED to do the Work.

Write for Full Particulars

26 Cortlandt Street,

New York City



ROCK DRILLING

INCORPORATED MINES PAYING DIVIDENDS.

	NAMES OF MINES	LOCATION	No. of Shares	Capital Stock	Par Value	Amount of Last Dividend	Date of Last Dividend	Total Amount Paid in Dividends	Kind of Mineral Produced
1	Aetna Cons.	California	100,000	\$ 500,000	\$ 5	\$ 10	July 1898	\$ 110,000	Q.
2	Ajax	Utah	300,000	3,000,000	10	10	October, 1897	1,000,000	G, C, S, L.
3	Alaska, Treadwell	Alaska	200,000	5,000,000	25	35 1/2	Oct., 1897	3,250,000	G
4	Alaska Mexican	Alaska	200,000	1,000,000	5	10	Oct., 1897	297,031	G
5	Alice	Montana	400,000	10,000,000	25	0 1/2	April 1898	1,075,000	G
6	Alice	Utah	40,000	10,000,000	25	0 1/2	April 1898	1,075,000	S, L, G
7	Anaconda	Montana	1,200,000	30,000,000	25	1 25	May 1898	6,750,000	C.
8	Anchoria Island	Colorado	600,000	600,000	1	0 1	July 1898	114,000	G.
9	American Gold	Colorado	800,000	8,000,000	10	0 2	Mar 1898	291,000	G, S, L.
10	Atlantic	Michigan	40,000	1,000,000	25	1 00	Feb. 1897	740,000	S.
11	Bald Butte	Montana	250,000	250,000	1	0 3	Sept 1897	512,500	G, C, S.
12	Bangkok O-Bell	Colorado	600,000	600,000	1	0 1	July 1898	107,510	S, L, C.
13	Big Six	Colorado	500,000	500,000	1	0 0 1/2	May 1898	15,000	G, S.
14	Boston & Montana	Montana	150,000	3,750,000	25	3 00	May 1898	7,625,000	G, C, S.
15	Bullion Beck and Champion	Utah	100,000	1,000,000	10	50	Mar 1897	2,485,000	G, C, S.
16	Bunker Hill and S.	Idaho	300,000	3,000,000	10	0 5	Oct 1897	321,000	S, L.
17	Cariboo	British Col	800,000	800,000	1	0 2	May 1897	156,965	G.
18	Calumet & Hecla	Michigan	10,000	2,500,000	25	10 00	Oct 1897	50,850,000	G.
19	Centennial Eureka	Utah	30,000	1,500,000	50	1 00	Mar 1897	2,010,000	S, L.
20	Central Lead	Missouri	4,000	400,000	100	1 00	Oct 1897	16,000	L.
21	Charleston	South Car	10,000	1,000,000	100	1 00	Feb. 1897	150,000
22	Champion	California	34,000	340,000	10	25	April, 1898	298,200	G.
23	Chloride Point	Utah	500,000	500,000	1	0 1	Dec. 1897	5,000	G, S.
24	Colorado Sun	Montana	100,000	1,000,000	10	30	June 1898	1,595,000	G, S, C.
25	Crescent	Utah	24,000	600,000	25	July 1897	280,000
26	Daly	Utah	150,000	3,000,000	20	25	Mar 1897	2,325,000	S, L.
27	Deadwood Terra	Dakota	200,000	6,000,000	25	40	June 1897	1,320,000	G.
28	De Lamar	Idaho	400,000	2,000,000	5	25	Jan 1897	2,250,100	S, L.
29	Della S	Colorado	1,000,000	1,000,000	1	10	Jan 1897	60,000	G.
30	Doe Run	Missouri	5,000	500,000	100	50	October 1897	L.
31	Elkton Consolidated	Colorado	1,250,000	1,250,000	1	0 1 1/2	July 1898	555,710	G, S.
32	El Paso	Colorado	650,000	650,000	1	0 1	Jan 1898	12,093	G, S.
33	Eureka Hill	Utah	10,000	1,000,000	100 1897	1,650,000
34	Florence	Montana	500,000	2,500,000	5	0 1	May 1897	132,530	S.
35	Gemini	Utah	5,000	500,000	100 1897	500,000
36	Geyser-Marion	Utah	300,000	1,500,000	5	0 2	May 1898	81,000	G.
37	Gold Coin of Victor	Colorado	1,000,000	1,000,000	1	0 1	June 1898	80,000	G.
38	Golden Cycle	Colorado	21,000	1,000,000	5	0 0 1/2	June 18 8	150,000
39	Gold Coin	Colorado	200,000	1,000,000	5	0 5	Nov 1897	140,000	G, S.
40	Gold and Globe	Colorado	750,000	750,000	1	3-10	July 1897	51,625	G
41	Hecla Consolidated	Montana	30,000	1,500,000	50	50	Feb 1897	2,175,000	S, G, L, C.
42	Helena & Frisco	Idaho	500,000	2,500,000	5	0 4	August 1896	475,000	S, L.
43	Highland	S. Dakota	100,000	10,000,000	100	20	Oct 1897	3,424,978	G.
44	Holy Terror	S. Dakota	300,000	300,000	1	0 3	Sept 1897	18,000	G.
45	Homestake	S. Dakota	125,000	12,500,000	100	25	Oct 1897	6,431,250	G.
46	Hope	Montana	100,000	1,000,000	10	10	Mar 1898	762,252	S.
47	Horn Silver	Utah	400,000	10,000,000	25	0 5	April 1898	5,120,000	S, L.
48	Idaho	Brit Col	500,000	500,000	1	0 5	Mar 1887	152,000
49	Iowa	Colorado	1,000,000	1,000,000	1	0 0 1/2	June 1898	90,000	G.
50	Iron Mountain	Montana	500,000	5,000,000	10	1 00	Jan 1898	501,100	S.
51	Isabella	Colorado	2,250,000	2,250,000	1	0 0 1/2	June 1897	270,000	G.
52	Kearsarge	Michigan	40,000	1,000,000	25	10	Aug 1897	140,000	C.
53	Last Chance	Brit Col	500,000	500,000	1	0 4	Jan 1897	42,000	S, L.
54	Le Roi	Britien Col	500,000	2,500,000	5	10	Oct 1897	625,000	G.
55	Lillie	Colorado	1,000,000	1,000,000	1	0 1	July 1898	99,100	G.
56	Minnesota	Minnesota	185,000	18,500,000	100	1 50	July 1896	3,240,000	L.
57	Montana Ltd	Montana	660,000	3,300,000	5	0 5 1/2	May 1898	2,097,557	G, S.
58	Montana Ore Purchasing	Montana	40,000	1,000,000	25	1 00	July 1898	760,000
59	Morning Star	California	2,400	240,000	100	5 00	June 1898	866,000	G.
60	Mt. Rosa	Colorado	1,000,000	1,000,000	1	0 2	Jan 1898	40,000	G.
61	Mercur	Utah	200,000	5,000,000	25	18	May 1898	1,066,000	G.
62	Mammoth	Utah	400,000	10,000,000	25	0 5	June 1898	1,250,000	G, S, C, L.
63	Moon Anchor Gold	Colorado	600,000	600,000	1	0 7 1/2	July 1898	218,000	G.
64	New Elkhorn	Colorado	300,000	1,500,000	5	24	Sep. 1896	72,001	G.
65	New York & Hon. Rosario	Central A.	150,000	1,500,000	10	10	Oct. 1897	832,500	S, G.
66	Napa	California	100,000	700,000	7	20	July 1898	950,000	Q.
67	New Idria Quicksilver	California	100,000	500,000	5	10	July 1898	60,000	Q.
68	Ontario	Utah	150,000	15,000,000	100	75	Dec. 1897	13,542,500	S, L.
69	Osceola	Michigan	50,000	1,250,000	25	1 00	June 1897	2,172,500	C.
70	Parrot	Montana	230,000	2,300,000	10	30	July 1898	2,000,898
71	Pennsylvania Consolidated	California	51,500	5,150,000	10	0 5	June 1898	38,775
72	Portland	Colorado	3,000,000	3,000,000	1	0 1 1/2	June 1898	1,492,898	G, S.
73	Princess	Colorado	1,000,000	1,000,000	1	0 0 1/2	Feb 1897	45,000	G.
74	Quincy	Idaho	100,000	2,500,000	25	4 00	August 1-97	9,470,000	C.
75	Rambler-Cariboo	Brit. Col	1,000,000	1,000,000	1	0 2	April 1897	40,000
76	Raven	Colorado	1,500,000	1,500,000	1	0 1	March 1898	20,000	G
77	Reco	Brit. Col	1,000,000	1,000,000	1	50 1/2	May 1897	187,500	S, L.
78	Sacramento	Utah	1,000,000	5,000,000	5	0 0 1/2	June 1898	35,000	G
79	Santa Rosalia	California	100,000	100,000	1	10	Feb 1888	125,000	G, S.
80	Small Hope Consolidated	Colorado	250,000	5,000,000	20	10	June 1888	3,340,000	S.
81	South Swansea	Utah	150,000	150,000	1	0 5	April 1898	90,000	S, L.
82	Standard	California	200,000	20,000,000	100	10	Mar 1898	5,651,940	G, S.
83	St. Joseph	Missouri	250,000	2,500,000	10	15	Oct 1897	21,000	L.
84	Silver King	Utah	150,000	3,000,000	20	25	June 1898	1,575,000	S, L, G.
85	Slocan Star	Brit. Col	2,000,000	1,000,000	0.60	0 5	Mar 1897	350,000
86	Smuggler	Colorado	1,000,000	1,000,000	1	0 1	June 1898	1,035,000	S, L, Z
87	Smuggler Union	Colorado	50,000	5,000,000	100	1.00	Oct 1896	150,000	G
88	Swansea	Utah	100,000	500,000	5	0 5	June 1898	100,000	S, L.
89	Tom Boy	Colorado	200,000	2,000,000	10	10	Dec 1896	600,000	G.
90	Tamarack	Michigan	60,000	1,500,000	15	3 00	June 1897	4,950,000	C.
91	Union	Colorado	1,250,000	1,250,000	1	0 1	June 1896	73,000	S.
92	Utah	Utah	100,000	1,000,000	20	0 1	Dec. 1897	177,000	G, S.
93	Utah Consolidated	Utah	30,000	150,000	5	0 2	Sept. 1896	3,0 0	S, L.
94	Victor	Colorado	200,000	1,000,000	5	50	June 1898	955,000	G.
95	Vindicator	Colorado	1,500,000	1,500,000	1	0 5	July 1898	76,125	G.
96	Western Mine Enterprise	Montana	500,000	500,000	1	20	Jan 1898	48,580
97	War Eagle	British Col.	500,000	500,000	1	0 6	October 1898	187,000

S, Silver. G, Gold. L, Lead. C, Copper. Q, Quicksilver. I, Iron. Z, Zinc.

**KLONDIKE MACHINE.**

If you are going to the Klondike, or any other country to place mining, you cannot afford to be without one of our placer machines. It will work any class of placer ground, river or sea sands. It will make a clean saving of the fine float gold as well as the coarse. The material is separated into four different grades in passing through the machine. A coarse screen is arranged over the hopper to cut out the rocks and gravel. It is fed regularly on to the screen below, a series of riffles are arranged at the end of this screen to catch any coarse gold that will not pass through the screen. The material then passes over the riffle table (a diamond) riffled on to the series over the amalgamating plates and cylinder, this fine screen cuts out all the coarse gangue, allowing nothing but the water and fine material to pass through the amalgamator, this avoids any scoring whatever. The screen and the riffle table and hopper has an end shake moving both together, can be set at any pitch, each separately, can be run fast or slow to suit the work being done. The machine is not the machine for dry countries as it requires very little water. By attaching one of our pumps the water can be used over and a large amount of work can be done with a small amount of water. The pump will lift water 20 feet from a stream or well. As a gold saver this machine has no equal it is light, simple, and durable, can be packed, the heaviest piece weighing 20 pounds, built almost entirely of metal, three sizes, price \$150, \$300, \$450, capacity to 25 and 40 tons, weight, 175, 400, and 650 pounds. **PACIFIC MINING MACHINERY CO.** Send for full descriptions. 129 Pirat St., San Francisco, Cal.

**The Pulsometer Steam Pump**

"THE MINER'S FRIEND" **Often Imitated—Never Equaled** **Over 20,000 in Use**

RECENT IMPORTANT IMPROVEMENTS

The Latest, Simplest and Most Efficient Steam Pump for General Mining, Conveying, Railroad, Irrigation, Draining, Coal Washing, Tank filling and for Pumping Back Liquids heavily impregnated with sediment. Mud or gritty liquids handled without injury to the Pump.

AGENTS

PARK & LACY CO., A. M. HOLTER HDW. CO., MITCHELL-Lewis & STAYER CO.
San Francisco, Cal. Helena, Mont. Portland, Oregon.

Pulsometer Steam Pump Co.

133 Greenwich Street, New York City

CATALOGUE ON APPLICATION
CORRESPONDENCE SOLICITED


The Bleichert Wire Rope Tramway

And Other Systems of Aerial Transportation



Bleichert Tramway of the Solvay Process Co. transporting rock

MANUFACTURED BY **THE TRENTON IRON CO., TRENTON, N. J.**
Engineers and Contractors, and sole licensees in North America for the Bleichert System. Also
Wire Rope Equipments for Surface and Underground Haulage, etc.
NEWTON H. BELL, Agent, 190 California St., San Francisco, Cal.



A Complete
Line of
Drills

Send for
Catalogue

UPRIGHT DRILLS

THAT ARE MADE BY

W. F. & JOHN BARNES CO.,
105 Ruby Street, Rockford, Ill

ARE SOLD IN
San Francisco by
HENSHAW, BUCKLEY & CO.

Established 1872.
F. E. BRANDIS, SONS & CO.
**ENGINEERING
INSTRUMENTS**
FOR ALL PURPOSES.
812-814 GATES AVE., BROOKLYN, N. Y.
Catalogues mailed on application.

Founded by Math. Carey & Co.
HENRY CAREY BAIRD & CO.,
Industrial Publishers, Booksellers and Importers
810 Walnut St., Philadelphia, Pa., U.S.A.
Our new and revised *Illustrated Catalogue of
Scientific Apparatus*, 750 pages, 8vo, complete to
February 1, 1900, and our other catalogues and
Circulars, the whole covering every branch of
science applied to the Arts, sent free of postage
to any one in any part of the world who will fur-
nish his address.

THEODOR LEXOW

195 Broadway New York

Importers of

CARBONS


— FOR —
DIAMOND DRILLS and all Mechanical
Purposes

Henry Demmert

I. C. YAWGER, VICTOR BISHOP & CO.



21 Maiden Lane NEW YORK

**DENVER PUBLIC ---
SAMPLING WORKS,**

M. E. SMITH, President.

ORES SOLD ON THE
PUBLIC MARKET. **Denver, Colo.**

MINERALS WANTED

Gold and Silver Quartz Specimens, Crystals,
Opals, Turquoise, etc., etc.

Buy in Any Quantities—Pay good prices—Cash

E. C. MOLLER.

538 EAST 86TH STREET,

NEW YORK

Dividend Paying and Investment Mining Stock

W. E. HUBBARD & CO.,

Tel. 505

15 W. 2d South St., Salt Lake City, Utah

GALDWELL BROS.

Tacoma and Seattle, Wash.

MANUFACTURERS AGENTS

AND DEALERS IN

MACHINERY and MINE SUPPLIES

We carry a Very Large and Complete Stock



It Will Pay You to Write Us for Quotations



BAKER & HAMILTON,

HIGH GRADE

Engines, Boilers, Ice Machines, Mining Tools, Etc., Etc.

THIS CUT represents our Single Engine PROSPECTOR'S HOIST, from 6 ft. P. up, constructed with sectional iron frame, reversible link motion, improved brake, etc. Engine and Hoist can be disconnected and used for other purposes. Hoist and Engine can be shipped knocked down, in pieces suitable for transportation over difficult roads and trails. We also carry Double Engine Hoists, same type, with or without Boilers, from 12 ft. P. up. This machinery is built in the most substantial manner possible, and on the most approved principles. We recommend them in every particular.

Write for Prices; They Will Interest You.

SAN FRANCISCO, CAL.

BRANCH HOUSES:
Sacramento and Los Angeles.

FACTORY:
Benicia, California

Expense

In the operation of Mines
is reduced by using our

Car Wheels.


Price and wearing qualities
reduce the expense.

Globe Iron Works

STOCKTON, CAL.

WRITE FOR PRICES.

EL PASO AUTOMATIC HORSE WHIM



This is the latest improved horse power hoist offered prospectors, possessing all the best features of other styles with improvements added. The end thrust is entirely done away with, thus increasing the efficiency and saving considerable wear. The automatic safety break is so arranged that accident is impossible, being in position until held out by operator to lower bucket. It is made entirely of iron and steel. Weight, about 1,200 pounds. Heaviest single-piece, 275 pounds. Price, f.o.b. Colorado Springs \$30. Cars, Buckets, Rope, Rails, etc. The El Paso Hoists. Manufactured by

The Hassell Iron Works Co.,
COLORADO SPRING, COLO., U. S. A.

UNION HARDWARE AND METAL CO.

DEALERS IN—

Boiler Tubes, Iron Pipe and Fittings

RAILROAD, MILLING, MINING and FOUNDRY SUPPLIES

14 and 216 N. Los Angeles Street

Los Angeles, Cal.

Assaying in all its Branches.

Determinations Accurately Made



The Bi-Metallic ...

Assay Office
and Chemical Laboratory

R. A. PEREZ, E. M., Manager

Formerly: Chief Assayer in El Paso Smelting Works, El Paso, Texas.
Assistant Chemist Consolidated Kansas City Smelting and Refining Co.,
Argentine, Kansas.

124 South Main Street,

Los Angeles, Cal.

IMPERIAL

(Trade Mark)

BOILER COMPOUNDS

For the Prevention and Removal of Scale—in Steam Boilers.

Please mail us a specimen of your Boiler Scale which we will analyze for you Free of Charge and prepare a compound for your special case, and guarantee satisfactory results.

ESTABLISHED 1876

IMPERIAL CHEMICAL CO.,

Indispensable to Mining and Mill Men


Office and Laboratory,

322 N. American Street, Philadelphia, Pa.

NORWALK IRON WORKS CO.

SOUTH NORWALK, CONNECTICUT.

THE NORWALK AIR and GAS COMPRESSOR



In use in every State in the Union, Central America, and South America, Great Britain, etc., Also used by the U. S. Army and Navy.

Especially Designed for
Driving

ROCK DRILLS,
PNEUMATIC LOCOMOTIVES,
ENGINES, PUMPS
COAL CUTTERS.

And Other Mining Machinery. The Best Machine for Compressing Air for all Dynamic Purposes. Send for Illustrated Descriptive Catalogue.


HENSHAW, BULKLEY & CO., Agents San Francisco

STEEL CASTINGS

From 1 to 40,000 pounds weight

Of Open Hearth or Chester Steel. True to Pattern, Sound, Solid. Gearing of all kinds and Crank Shafts, Shoes, Dies, Crusher Plates, Bosses, Tappets and Roll Shafts. Steel Castings of every description.

Chester Steel Castings Co.,
Works Chester, Pa., Office, Library St.
Phila., Pa.



Randsburg Gold Fields VIA Santa Fe Route

Leave Los Angeles, 9:50 a. m.
Leave San Bernardino 12:10 p. m.
Arrive Barstow 2:15 p. m.
Leave Barstow 3:55 p. m.
Arrive Kramer, 5:05 p. m.
Arrive St. Elmo, 6:25 p. m.
Arrive Johannesburg 8:50 p. m.

Returning Trains Leave
Johannesburg 9:00 p. m.
Arrive San Bernardino 6:35 a. m.
Arrive Los Angeles, 8:25 a. m.

A through passenger coach is run between Barstow and Johannesburg.

Through tickets and particulars of any Santa Fe Route Agent.

Stage leaves Johannesburg for Ballarat on Sundays and Thursdays at 7 a. m.; returning arrives at Johannesburg on Tuesdays and Fridays at 8 p. m.

SAN FRANCISCO OFFICE

644 MARKET ST.

LOS ANGELES OFFICE

200 S. SPRING ST.



BUFF & BERGER Mining Transits

With patent interchangeable auxiliary. Telescope for use on top or side in vertical sighting. Our friends are cautioned against infringements foreign or domestic as attempts have been made of late to mislead the public.

SEND FOR CATALOGUE.

11 Province Court, Boston, Mass.

Mines Examined

Processes Tested

HORACE F. BROWN, M. E.

PATENTEE OF
BROWN'S SYSTEM OF MECHANICAL ROASTING
FURNACES, Complete Automatic Milling
Processes, Etc.

1606-7 MANHATTAN BLD., CHICAGO

JOHN STEWART

MINING ENGINEER

Address—Mining and Metallurgical Journal
LOS ANGELES, CAL.

Examines and Reports on Mineral Properties

Ores! Ores! Ores!!

Gold, Silver and Lead Ores and Concentrates

Purchased at Reduced Rates for Treatment.

Selby Smelting and Lead Co.

416 MONTGOMERY ST., San Francisco

Consign Shipments to Vallejo Junction, Cal.

W. O. ABBOTT, ASSAYER

ASSAYING IN ALL ITS BRANCHES
CHEMICAL DETERMINATIONS ACCURATELY MADE

TOMBSTONE - - - ARIZONA

Spadone's Concentrator Belts

Patented



This illustration shows the edge flanging outwardly as it passes over the pulley. This relieves the strain from the top and bottom of the edge by directing the strain automatically to the inside face surface of the edges. Heretofore all belts have been so constructed that when they pass over the pulleys or rolls, a direct strain comes upon the top or at the base of the edges, causing the edges to break away from the body of the belts in a very short time. We avoid this Mechanical Defect by our Spadone Curved Edge Belts made to fit any machine—4, 5 and 6 feet wide. Prices and samples on application.

Send us your order for Water, Air Drill, Steam, Suction and Fire HOSE, RUBBER BELTING, RUBBER PACKING and LEATHER BELTING.

The Gutta Percha Rubber and Manufacturing Company,

30 and 32 FREMONT STREET,

SAN FRANCISCO, CAL.

MATTISON & CO.

29 LIBERTY ST.,
NEW YORK CITY

BUY

ANTIMONY ORES AND

CRUDE ANTIMONY

* WRITE FOR FULL PARTICULARS

Minerals Wanted

Ores, Crystallized Specimens, Loose and detached Crystals
Wanted in Quantity

If you have any Ores, Unidentified, write me.

ROY HOPPING,

5 and 7 DEY STREET,


NEW YORK CITY



C. DUCOMMUN,

300-302 N. MAIN STREET,


LOS ANGELES



Assayers Material Mine and Mill Supplies

Dixon's Black Lead Crucibles, Denver Fire Clay Crucibles, Muffles, Scorifiers, etc.; Quicksilver, Drill Steel, Retorts, Mortars, Gold Pans, Drilling Hammers, Drifting Picks, Horn Spoons and Shovels

Half Universal Radial Drills



The special features which have so highly recommended this style of Drills are our double columns, steel gearing, power and hand feeds, quick return motion to spindle. Furnished in three sizes, with large variety of tables, adapting the drills for every class of work possible.

Bickford Drill and Tool Co.

CINCINNATI, OHIO, U. S. A

HENSHAW, BULKLEY & CO., AGENTS • San Francisco, Cal.

WHITNEY COMPANY

Iron and Steel. Miners, Blacksmiths, Machinists Supplies

Agents for Arizona and New Mexico for Marsh Steam Pump, Agents Hercules High Explosives, Miner's Supplies by Car Load, Fairbanks Morse Hoisting Machinery and Engines. Full Line of Steam Fittings and ENGINEERS Supplies. A specialty made of Supplying the Mining Trade of the SOUTH-WEST

ALBUQUERQUE

*

*

*

NEW MEXICO

When Installing a Tramway Have the


Finlayson Patent Automatic Wire Rope Tramway

The Only Automatic
(Double rope) Tramway Built

Economy
in Operation

Simplicity in
Construction

Easy
Running



CHALLENGE ECLIPSE ORE FEEDER
Will feed both wet and dry ores

THE COLORADO IRON WORKS COMPANY,

ESTABLISHED 1860

DENVER, COLORADO.

SOLE MANUFACTURERS

ENGINEERS AND MANUFACTURERS OF

Ore Milling and Smelting Equipments

CATALOGUE ON APPLICATION



BLACK HAWK ORE BREAKER

A. A. BAILEY

MANUFACTURER AND DEALER OF THE LEADING

Packings and Engineers Supplies

LUBRICATING OILS AND COMPOUNDS

Exclusive Manufacturer of the UNSURPASSED

BAILEY


Anti-Friction Metal and all other Grades of Babbitt Metal

Sole Agents for Reliable Steam Pumps

300 South Los Angeles Street, LOS ANGELES, CAL.

Geo. F. Blake Mfg. Co.

NEW YORK, N. Y.



Boiler Feed Pumps,
Tank or Light Service
Pumps,
Combined Air and Circulating
Pumps,
Drainage and Irrigating
Pumps,
Special Fire Pumps,
Independent Air Pumps
and Condensers
Water Works and Power Pumps.

Henshaw, Bulkey & Co., Agents. San Francisco, Cal.

"READY ROCK" ASPHALT ROOFING

* THE STANDARD ROOFING OF THE UNITED STATES

Absolutely the most durable, convenient and strongest roofing material made.

"Ready Rock" Asphalt Roofing Co.

1006 North Main Street,

TELEPHONE MAIN 1570

Los Angeles, Cal.

Why SEND YOUR MONEY EAST FOR

Shoes and Dies, Camp Tappets, Car Wheels, Shafting, Hangers,
Pulleys, Ore Cars and Iron and Brass Castings, when they can
be obtained for the same price and in less than half the time

AT THE

Albuquerque Foundry and Machine Works,

Repairing of Mill and Mining Machinery a Specialty, Albuquerque, New Mexico

**F. A. A. WILLIAMS,
Mines & Mining**A free Milling Gold Property at a bargain
Correspondence Solicited

TRINIDAD, COLORADO

N. D. BURLINGHAM, M. E.

Practical Examination of Mines
anywhere. Plans and estimates
for Mining Machinery on
short notice.

FOURTY YEARS EXPERIENCE IN MINING AND MILLING
310 W. FIRST STREET, LOS ANGELES.

ASSAYERS AND CHEMISTS

Working tests of Ores by all processes
Samples by mail or express solicited

TREMAINE & FROELICH,

132 Third St., PORTLAND, OREGON

CHICAGO SCHOOL OF ASSAYING,

J. DUNRAVEN YOUNG, Director.
1759 MONROE BLDG., CHICAGO, ILL.
Courses in Elem Chemistry, Chemical Analy-
sis, Fire Assaying of Gold, Silver, Copper and
Lead Ores, etc. Ore Testing, including Mill
Runs by Mercury, Cyanide and Chlorination
processes. Individual instruction only. Open
evenings. Opportunity for Miners & Prospectors

Harper & Reynolds Co.,*** MINING + SUPPLIES ***

— AGENTS FOR —

Judson Dynamite and Powder Co., Galvanized Spiral
Pipe, Steel and Iron.

152-154 North Main Street, } LOS ANGELES, CAL.
151-152 North Los Angeles Street, }



California Bellows Manufacturing Co.
123 Beale St., San Francisco, Cal.

BLACKSMITH BELLOWS

And Bellows of Every Description


Write us for our new catalog

THE CHEAPEST PLACE ON EARTH


TO OUTFIT A MINE IS AT

The J. H. MONTGOMERY MACHINERY CO.,

1220-22 Curtis St., Denver, Colo., U. S. A



Just Listen—Reliable
Sensu Steel & Iron
up; hand boiler
buckets all price
stamp mills and A the
stamp mill, no
80 lb. stamp
high mill

**QUEEN NO. 4 ASSAY BALANCE**

Aluminum Beam, Scale Rulers and Plates
Sensitivity two mg. The Best Low Price Assay
Balance on the Market. Send for Circular

QUEEN & CO.,

Optical and Scientific Instrument Works
1010 Chestnut Street,
N. Y. office, 115 Fulton St. Philadelphia

ESTABLISHED IN 1840

HENRY TROEMNER,

710 Market St., Philadelphia, Pa

**Assay Balances and Weights**

In use in all the U. S. Assay Offices
in America

PRICES LIST ON APPLICATION.

"HENDY" IMPROVED**Triple Discharge Two-Stamp****— MILL —**

Capacity six to ten tons per day

JOSHUA HENDY MACHINE WORKS

38 to 44 Fremont St., San Francisco, Cal.

ROGERS & BALDWIN,**MACHINE SHOPS**

All kinds of repairing
for Engines, Boilers
and Machinery

Riverside, Cal.

ANTIMONY.

We buy Antimony Ore in any
quantity and pay prompt CASH for same.
Write us and let us know what you
have

Chapman Smelting Works Co.,

224 Battery Street San Francisco, Cal.

**JEFFREY****ELEVATORS****CONVEYORS****WIRE CABLE CONVEYORS**

THE JEFFREY MFG. CO.
Columbus, Ohio.

Western Branch, - - - - - Denver, Colorado

P. H. HENDY, MANAGER

**Quartz Screens**

A specialty. Round, slot or lined slot holes. Genuine Russian Iron, Homogeneous Steel, Cast Steel or American planished Iron, Zinc, Copper or Brass Screens for all purposes. CALIFORNIA PERFORATING SCREEN CO., 115-117 Beale St. S. F.

E. C. WOODWARD,
Assayer and Chemist

Telephone 315

24 E. Kiowa St., Colo. Springs, Colo.

KLONDIKE

WANTED—Men & 1 woman to know the cheapest, easiest and best way to make experience on the way to the Klondike. Apply at 1036 First St., Portland, Or.

Pacific Coast and Mexican Agents

— FOR —

Kearby & Mattison's



ALL KINDS OF ASBESTOS GOODS

DE SOLLA DEUSSING COMPANY,

**Magnesia Sectional
Steam Pipe and Boiler
Covering**

The only Covering that water will not destroy. Indispensable in covering pipes conducting steam to pumps in mines.

Send for Testimonials.

4 California Street, San Francisco, Cal.

EDWARD B. READ,

Engineers' Specialties, Cylinder and Machinery Oils, Cylinder Lubricators,

LORD'S BOILER COMPOUND, Cyclone Steam Flue Cleaner, Engine Compound Electric Spiral Packing, Shafting Compound, Crank Pin Grease, Wire Rope Grease, Extra Gear Grease, Belt Grease and Oil, Skin Grease, Elevator Grease, Crescent Flue Scraper, Oil Cups, Compound Cups, Dibble Lubricator, Packing and engineers' supplies. CORONADO WHEELS.


No. 12 First Street,

San Francisco, Cal.

NEW HAVEN MFG. COMPANY

NEW HAVEN, CONN.

**IRON
WORKING
TOOLS,**



Engine Lathes, Pulley Turning Lathes, Iron Planers, Slotters, Upright Drilling Machines, Horizontal Drilling and Boring Machines, Etc.

HENSHAW, BULKLEY & CO., Agents, San Francisco, Cal.

**SMITH & THOMPSON**

Manufacturers of

Fine Assay Balances

Write for Catalogue

2210 Stout street

Denver, Colo.

J. B. Pope

U. S. Mineral Surveyor,

SAN BERNARDINO, CAL.

The Giant Powder Company

+ CONSOLIDATED +

Principal Office: 430 California Street
SAN FRANCISCO, CAL.

*

P. J. NOLAN, General Agent for Mexico
Apartado 230 CITY OF MEXICO.

*

A. A. SPARKS,
Resident Agent Southern California.
Room 438 Bradbury Block, LOS ANGELES, CAL.

AGENTS

Roy & Titcomb, Nogales, Arizona
Samuel Hill, Prescott, Arizona
Kellner's Store, Phoenix, Arizona
Thomas Wilson, Tucson, Arizona

A. Calderon, Hermosillo, Mexico
G. Moller & Co., Guaymas, Mexico
Wohler Bartling & Co., Mazatlan, Mex.
Delius & Co., San Blas, Mexico

Julio Hilderbrand & Co., Durango, Mexico
Julio Hilderbrand & Co., Tofia, Mexico

J. P. De Fresno, Culiacan, Mexico
T. Robison Boura, Alamos, Mexico

Manufactures Dynamite, Black Blasting and
Sporting Powders.



TANKS

OF EVERY DESCRIPTION

— FOR —

**Mines, Mills and Cyanide Plants
Patent Non-Shrinking Water Tanks**

The only Tank that will stand the Desert and Hot Climate.


Write for Catalogue and Estimate on any kind of Tank Work.

Pacific Tank Co.

33 BEALE ST.,

SAN FRANCISCO

318 EAST 2d STREET, LOS ANGELES



To Gold Miners!

Silver Plated Copper AMALGAMATING PLATES

For Saving Gold In Quartz and Placer Mining.

EVERY DESCRIPTION OF MINING PLATES MADE.

Only Best Copper and Refined Silver Used. Old Mining Plates Replated. Twenty-six Medals Awarded. Gold, Silver, Nickel, Copper & Brass Plating.

Denniston's San Francisco Plating Works

653 and 655 Mission Street, San Francisco, Cal.

— Telephone, Main 5931. —


Proprietor

E. G. DENNISTON,

Send for Circular.

Foos Gasoline and Distillate Engine

The Best in the Market



Ten Engines lately put in the Rand District operating Hoists, Mills and Pumps. We have sold 100 of these engines and we warrant them satisfactory. The Triumph Pump for deep wells throws a steady stream. No cranks or dead centers. The rods move vertically require less power than other pumps.

Sudebaker Vehicles,
Machinery, Engines

S. W. LUITWEILER CO.

200-202 N. LOS ANGELES ST.
LOS ANGELES, CAL.

ESTABLISHED 1859

Herman Kohlbusch Sr.

59 Nassau Street,
New York, N. Y.


MANUFACTURER OF

**Fine Balances
and Weights**

For every purpose where accuracy
is required.

...

Send for Illustrated Catalogue



THE WILSON

Forged High Grade Steel

Shoes and Dies

Guaranteed to Wear Longer and Prove Cheaper than any others.
Made by use of Special Appliances. Patented Aug. 16th, 1891.

— Made only by —

WESTERN FORGE AND ROLLING MILLS

St. Louis, Missouri

JOSHUA HENDY MACHINE WORKS

SOLE AGENTS

38 to 44 Fremont Street,

San Francisco, Cal.

The JACKSON Hand Power Rock DRILL

NO JAR

EASILY OPERATED


We also deal in General Mining Machinery and Supplies

The Jackson Drill and Manufacturing Co.
N. Y.—OFFICE,
120 Liberty StreetExhibition Rooms,
1709 California St.,

DENVER, COLORADO, BOX 1362

Office on
1767 Lurline St

CABLE ADDRESS: "Jack Drill," New York, A. B. C. Code 4th Edition and Lieber.



The National Feed Water Heater

Highest Premium at World's Fair

800,000 HORSE POWER IN USE

SIMPLICITY
CHEAPNESS
RELIABILITY
EFFECTIVENESS

Henshaw, Bulkley & Co.,

Agents,

SAN FRANCISCO, CAL.




P. & B. PAINT

FOR MINES, SMELTERS, CHLORINATION WORKS,
THE CYANIDE PROCESS.P. & B. Roofing put up in Rolls to lay 200 square feet, with Paint and Nails.
Absolutely Acid and Alkali Proof.

PARAFFINE PAINT CO., Manufacturers, 312-314 W. 5th St., Los Angeles

The Eynon-Korting Compound Injector

The Best for
Quartz Mill
and Smelter
BoilersBrass, Bronze and Copper Castings of every description.
Send for Catalogue of the
Injectors, Condensers, Blowers, Ventilators, Blast Nozzles,
Syphons, Exhausters, Etc.THE EYNON-EVANS MFG CO.,
15th and Clearfield Streets, PHILADELPHIA, PA

E. C. CREEL, Presidente.

JUAN A. CREEL, Gerente

Compania Industrial Mexicana

Ferreria
Fundicion de Fierro y Bronce


Fabricantes...

de toda clase de

Maquinaria para minas y
Haciendas de Beneficio

Quebradoras Maquinas de vapor.

Retortas, Ruedas Hidraulicas, Calderas
de todas clases, Maquinas de extraction. Car-
ros para mineral, Molinos Huntington. Bombas
Malacates de Vapor panes de amalgamacion.
Concentradores, compresores de aire. Lavaderos,
Haciendas de Lixiviacion: Hornos de chaqueta
["Water Jackete."]



Dinamos, Motores y Material
Electrico.

BARATURA y PRONTITUD.

Se envian circulares Pedido.

Se solicita la correspondencia.

Para informes dirigirse al gerente,

JUAN A. CREEL,

Chihuahua,

Mexico





W. T. GARRATT & CO. Brass and Machine Works.

MANUFACTURERS

HOOKER STEAM PUMPS,
MINERS' SINKING PUMPS,
TRIPLE PLUNGER PUMPS,
JACKHEAD MINING PUMPS,
CENTRIFUGAL PUMPS,
GONGS FOR MINE SIGNALS,
LUBRICATORS & OILERS,
SUCTION HOSE AND COUPLINGS,
HYDRAULIC PIPES,
IRON PIPE AND FITTINGS
BABBITT METALS,
PACKINGS
REPAIRING PROMPTLY ATTENDED TO.

138 to 148 Fremont Street,
SAN FRANCISCO, CAL.



MINERS' OUTFITS.



IRON MORTARS,
AMALGAM MORTARS,
GOLD WASH PANS,
MINERS' HORNS,
BATEAS, CRUCIBLES,
HORSE-SHOE MAGNETS,
MAGNIFYING GLASSES,
IRON RETORTS,
CHEMICALS, SCALES,
WEIGHTS, ETC.

Including a full as-
sortment of Mine and
Mill Supplies, Assay-
ers' Materials, Etc.

Sole Agents for the
Pacific Coast for the

W. S. TYLER WIRE WORKS CO.
Manufacturers of

Steel and Brass Wire Battery Screens
Agents for Baker & Adamson's Chemically
Pure Acids. A full Stock always
on hand.

Nitric Acid, sp. gr. 1.42; Muriatic Acid, sp. gr.
1.20; Sulphuric Acid, sp. gr. 1.845.

JOHN TAYLOR & CO.
83 FIRST ST., SAN FRANCISCO
Prices on application

The State Ore Sampling Co.

DENVER, COLORADO.

Gold, Silver, Lead and Copper Ores and Matte
sampled and marketed to the best advantage.
With modern mills and machinery our facilities
for sampling ores are the best.
Our long experience in the market enables us
to obtain the highest prices for all marketable
ore. Write for our "Reference Book." Send
analysis of your ore for prices and information.

BAILY & MONNIG, Managers.

Silver City Reduction Company

This plant has been purchased and will be
operated in the future by the Estate of the late
Senator George Hearst of California, under the
general management of D. B. Gillette, Jr.
It is the intention of the present management
to largely increase the capacity of the plant and
equip it with every modern appliance for the
successful and cheap treatment of ores and con-
centrates.

Consignments and Correspondence Solicited
Advances will be made on ores.

Silver City, Grant Co. New Mexico




FULTON ENGINE WORKS

Mining, Milling and Smelting Machinery

Estimates Furnished on all Classes of Mining Work

P. O. Box 296, STATION "C"

LOS ANGELES, CALIFORNIA



FACTORY:

3101-3141 Blake St., 1742-1746 Champa St., Denver, Col.

Analytical Chemists and Assayers

Analysis made of ORES, Waters,
Chemicals, Clays, &c. Umple
Work a Specialty

HAMLIN & MORRISON,
141 Chestnut Street, PHILADELPHIA, PA.

TIMOTHY W. SPRAGUE, S. B.

WITH

CHARLES HENRY DAVIS, C. E.
CONSULTING ENGINEERS

99 CEDAR ST., NEW YORK 4 STATE ST., BOSTON
DREXEL BLDG., PHILADELPHIA
Electric Transmission of Power and Mine
Equipments

FAUTH & COMPANY,

(O. N. SAROMULLER),

Engineering and Mining Instruments,
WASHINGTON, D. C.

Attention is called to our newly improved
Mining Transit, with best Solar Attachment
and Vertical Sighting Telescope and Quick
Leveling Head.

This Cut Illustrates Our
4 H.P. to 8 H.P.


Hoisting Plant

We also build larger sizes to suit
the demands of our
customers.

The Hoist Illustrated is designed to lift 1,000
pounds 120 feet per minute with the smaller
sized engine.

It is strong and exceedingly simple and dur-
able, being entirely under the control of the
operator, by the use of a single hand lever for
hoisting, while the lowering is governed by a foot
lever and brake.

No better device has been designed for this
purpose.
For prices and further information address the
builders.



ORIENTAL GAS ENGINE CO.

105 Beale Street, San Francisco, Cal., U.S.A.

WHITE, ROGERS & COM'Y.

CONSTRUCTING ENGINEERS AND MILLWRIGHTS

306 PINE STREET, SAN FRANCISCO, CAL.

Sole Pacific Coast Agents and Builders of the Celebrated

WILFLEY CONCENTRATOR,

Price \$450 f.o.b. San Francisco

One of these Machines will take the place of TWO or THREE Belt Concentrators of any make and do very much better work.



WILFLEY CONCENTRATOR

We furnish superior Machinery and erect Stamp Mills, Hoisting and Pumping Works
operated by Steam or Water Motors. Complete Concentrating and Smelting Plants for the
concentration and recovery of gold, silver, copper and lead. Improved Power Drills and Air
Compressors, Wire Rope Tramways, etc.

The Wilfley Table is fully covered by U. S. Patents Nos. 580,338 and 590,675.
Infringements will be prosecuted to the full extent of the law.

These Machines are Kept in Stock Ready for Immediate Shipment

Chicago and Aurora Smelting and Refining Co.

PURCHASERS OF
Lead, Silver and Gold Ores
 Works at Leadville, Colo., Aurora, Ill., and Chicago, Ill.
 General Office, Woman's Temple, Chicago, Illinois

GOLD and SILVER REFINERS & ASSAYERS.

Bullion Bought. No charges for parting: Gold \$20.10 per oz., Silver and Platinum at market prices. Assaying in all branches. Working tests made by all processes. Wastes and Concentrates bought. Prompt attention. Best Services. Your Trade Solicited.

PENN SMELTING AND REFINING WORKS, 901 903 Filbert St., PHILADELPHIA, PA

"Keep Your Eye on the Indicator"


The Bolthoff Signal Alarm Indicator

Hundreds Now In Use. Universally Recommended.

It is without question the most accurate indicator for hoisting engines ever constructed. Not only is there no lost motion, but it has the valuable feature of a device whereby automatically the approach to station, curves in the shaft, bad places, or obstructions, or, in fact, if for any reason the engineer desires to be warned of the approach of the cage or bucket to any particular point in his shaft, either in hoisting or lowering, he can set it so that the signal bell will automatically sound its alarm.

HENDRIE & BOLTHOFF M'FG. & SUPPLY CO.,

Denver Colorado, U. S. A.

The New Improved Wonder Mining Pump

The only Mining Pump made that will work from pump to pump on the one discharge pipe, doing away with all reservoirs. Write

The Wonder Pump Manufacturing Co.,

ARMOUR BLDG., KANSAS CITY, MO., for catalogue

Stockton Assay Office

Gold and Silver Assays, \$2.00.
 Five Assays and over, \$1.50 each

329 E. Magnolia street, Stockton, Cal.
 Send Samples and remittances by Express or mail.

Third Edition Revised and Enlarged.

Prospector's Field Booke and Guide

In the search for and the easy determination of another useful minerals, by H. S. Osborn, of 38 engravings 224 pages, by mail \$1.50.

Catalogue of Mining, Assaying, etc., sent free.
PHILADELPHIA BOOK CO.

15 S. Ninth Street,

Philadelphia, Pa.

EAGLE PACKING

Also White Eagle, Graphite, Hydraulic, Nitr and other brands for all purposes for which packing is used. Write for samples and prices. Manufactured by James Glandling Co., 1927-9 North 6th St., PHILADELPHIA, PA.

Mathematical, Scientific and Drawing Instruments



Boxwood Scales. All kinds of repairing promptly executed. GUIDO FERRARI

S. E. Cor. 7th & Chestnut Sts., Philadelphia, Pa.

Turbine AND Cascade WATER WHEEL


Adapted to all Heads from

3 Feet to 2000 Feet

Our experience of 33 YEARS building Water Wheels enables us to suit every requirement of Water Power Plants. We guarantee satisfaction.

Send for a Pamphlet of either Wheel and write full particulars.

James Leffel & Co.
 SPRINGFIELD, OHIO, U.S.A.




\$35,000,000 in Dividends paid out by Utah Mines up to date.

UTAH MINING STOCKS

Weekly Market Report on application. Quotations by wire or mail.
 Reference: Any Bank in Salt Lake City.

P. J. CONWAY & CO.,

SALT LAKE CITY, UTAH

**DANIEL'S PATENT P.P.P. Diagonal Rod Packing**

For Steam, Water, Oil, Air, Ammonia, Etc.

SAVES LABOR
 SAVES POWER
 SAVES MONEY

It Represents Highest Class Materials and Greatest Service.

**NO PAY IF NOT AS CLAIMED**

SLIDING WEDGES, COMPENSATING FOR WEAR. OIL CUSHION TO ENAMEL AND LUBRICATE THE ROD.

Best Packing for use in MILLS, MINES and SMELTERS

MANUFACTURED ONLY BY

C. A. DANIEL, Philadelphia, Pa.

To insure getting the Genuine see that Every Box and Wrapper has our Trade Mark.

THOMAS PRICE & SON

Analytical Metallurgical and Physical Testing Laboratory

524 SACRAMENTO STREET, SAN FRANCISCO, CAL.

N. OHLANDT & CO.

MANUFACTURERS OF

Best Quality of BONE ASH for Assayers.

Our Goods are used in all parts of the United States and Mexico.

EXTRA No. 1 and No. 2

CORRESPONDENCE SOLICITED

327 MARKET STREET, SAN FRANCISCO, CAL.

Miners Attention!

We Sell Powder, Caps, and Fuse, Mining Machinery, Belting, Asbestos Goods, packing of all kinds, Picks and Shovels, Iron and Steel; Iron Wheelbarrows, Ore Sacks, Tents, Portable Forges and General Mining Supplies. Agency Truax Mfg. Co and Studabaker Wagons.

WILCOX & ROSE CO.,

San Bernardino, Cal.



Engineers' and Draughtsman's Supplies

Sole agents for Riefler's round system drawing instruments and Albert Ott's Planimeters, Planigraphs and other instruments of precision. Levels and transits of superior make.

P. WEBER & CO. PHILADELPHIA

1125 CHESTNUT ST.,

Subscribe for



the Journal

**Pueblo Foundry,
Machine Shops and
Boiler Works**

— MANUFACTURERS OF —

Wrought and Cast Iron Water Jacket Furnaces, MINING and Irrigation Pumps, Engines, Boilers, Holsters, Tanks, Derricks, MINING MACHINERY, Brass Castings; light and heavy Forging. New and Second-hand Engines, Boilers and pumps always on hand.

PUEBLO, COLORADO.

The Machinery and Electrical Company,**Machinery and Supplies**


MINING HOISTS, WHIMS, ORE BUCKETS,
Bates Corliss Engines, Snow Steam Pumps
OIL CITY BOILERS AND ENGINES,
Hercules Gas Engines, Lawrence Centrifugal Pumps
GATES IRON WORKS MINING MACHINERY
Tremaine Steam Stamp Mills
Electric Lighting, Railway and Transmission Apparatus
Washburn & Moen Mfg. Co's Wires and Cables

Also Dealers and Jobbers in

Shafting, Belting, Dodge Wood Pulleys, Hangers, Boxes, Etc.

WRITE FOR PRICES

351 & 353 N. Main St. Los Angeles, Cal.



TREMACHINE STEAM STAMP

**HALLIDIE
PATENT
ROPEWAY**

— FOR THE —

Transportation of Ore, Fuel and other material, has been erected by us all over the country and is the most economical and efficient method known. Nothing to get out of order; has always given satisfaction.

California Wire Works

(LICHTENBERG)

Office, 330 Market St. San Francisco, Cal.



Mention the Journal

EASTERN PRICES BEATENIMPROVED FACILITIES, FINEST WORK
LOWEST PRICES**PERFORATED SHEET METALS**

For Flour and Rice Mills, Grain Separators, Shaker Screens, Gravel and Cement, Revolving and Shot Screens, Stamp Batteries, Iron, Steel, Russia Iron, American Planish, Zinc, Copper and Brass Screens for all uses. Inventor and Manufacturer of the celebrated Slot Buried and Diagonal Slot punched Screens.

MINING SCREENS A SPECIALTY

Mill owners using screens extensively, can contract for large supplies at favorable rates. J. W. QUICK is the only competent and successful manufacturer of Screens on the Coast, having furnished Screens to the Principal Mills of

California, Nevada, Alaska, Mexico, Arizona, Central America, Australia and British Possessions.

San Francisco Pioneer Screen Works

(Established 1863)

221 and 223 FIRST STREET, SAN FRANCISCO.

J. W. QUICK, Prop.




MANUFACTURER AND DEALER IN

Perforated Sheet Metals,

Steel, Russian Iron, American Planished Zinc, Brass and Copper.

Mining Screens of Every Description
SAN FRANCISCO, CAL.

**AINSWORTH NO. 043**

Sensibility.....1-100 Milligramme

Ten inch beam on which you can weigh from 1-100 to 1 Milligramme with a one milligramme rider.

Complete catalogue of Assayers' and Chemists' supplies, including this and other balances, mailed upon application. SELLING AGENTS,

The Denver Fire Clay Co.,

1742-1746 Champa St., Denver, Colo.
P. O. BOX, 1640

The Kootenai Gold Mining District

of British Columbia, which of late has been attracting considerable attention, is best reached by the Oregon Railroad and Navigation Co. The fact has recently been brought out that the Kootenai district contains within its borders more *High Grade Silver and Lead Mines* than any other part of the world. The recent discoveries of *Rich Gold Lodes* makes it the most attractive country for the *Capitalist Miner and Prospector* to visit in search of mines.

The Oregon Railroad and Navigation Co.

Dispatch Fast Steamers every Four Days

from San Francisco connecting at Portland, Oregon with their rail line for all points in this famous district. For full particulars address,

E. C. WARD, GENERAL AGENT.

630 Market Street,

SAN FRANCISCO, CAL.

**WIRE
TRAMWAYS**

Ropeways,

* Incline Planes,
and Railways.

Holisting Apparatus, Patent Grip Pulleys, Transmission of Power by Wire Ropes; 25 years experience; Send for Ropeway Pamphlet.

Pacific Coast Agents for

The Calhoun Excavator

A combined power Shovel and Cableway for excavating and handling earth or loose rock.

SEND FOR DESCRIPTIVE CIRCULARS

Witte Gasoline Hoister



Uses Gas, Gasoline, Distillate, Naptha or Kerosene. Requires no Coal, Wood or Engineer and little water. Guaranteed absolutely safe, reliable and durable. Single or Double Drums, Right or Left Handed Geared or Friction.

CHAS. B. BOOTHE & CO.,
LOS ANGELES, CAL.

WITTE IRON WORKS CO.,

1201 Walnut Street,

Kansas City, Missouri

Send for Catalogue B

HOME MANUFACTURE FOWLER'S

Fossil Asbestos Manufacturing Co.,
Sectional Removable Covering
for Steam Boilers, Pipes, etc.
As a Non-Conductor, Unequaled
Absolutely Fire Proof

O. C. FOWLER, 656-58 Howard Street,
San Francisco, Cal.



HOFF ASBESTOS MFG. CO., Bryson Block,
Los Angeles, Cal., Agent for Southern Cal


H. P. C. COATES, MINING AND DIVIDEND PAYING STOCKS,

Reliable Information on Application

SALT LAKE CITY, UTAH

FOUR and SIX FOOT FRUE VANNERS

With Brownell "Patent Lip" Flange Belts



After a Concentrator like the Frue Vanner has been on the market nearly two decades, and the sales have constantly increased, it is safe to say it is the "Standard Machine of the world." More Frue Vanners have been sold during the last twelve months than for the same period at any time during the history of the machine. Practical mining men in all parts of the world where mining is carried on will testify as to its merits. It is the "Standard" which all competitors are trying to imitate.

The results obtained by this machine are the "Acme" of concentration, and several cheap and untried machines that have lately come on the market compare by it, and the manufacturers will tell you that they are "just as good, and cheaper, etc." The facts are that no other concentrator made has an equal capacity, or will yield as clean a concentrate with as small loss in the tailings as the Frue Vanner. The amount saved from the lower first cost of an inferior machine counts little in the years results, when compared with the increased output from a Frue. This machine not only gives better results at both ends of the belt (i. e. Clean product and poor tailings), but is operated at less expense and requires less attention than any other machine on the market. At the Alaska Treadwell Mine where they have ordered over 350 Frue Vanners one man attends 48 machines for 12 hour shift.

FOR DESCRIPTIVE PAMPHLETS, ADDRESS


JAMES S. BROWNELL, Western Agent
132 Market Street.

FRUE VANNING MACHINE CO.

(Successor to Adams & Carter)

SAN FRANCISCO, CAL.


PERKINS Gas Engine



MODEL OF 1897

Composed of Sixteen parts, constructed so plain and substantial that it may be taken to the desert mines without fear of unreliable operations, uses storage and dynamo for sparking, the cooling jacket water is used over. Uses about 8-10 of a gallon of gasoline for each horse power for a twelve-hour run. Ten horse power engine weighs 2250 lbs. boxed for shipment.

Perkins Power Hoist



Is light and portable weighing 1050 lbs., heaviest piece weighs 150 lbs., capacity 1000 lbs. one hundred foot per minute will lift 400 feet. A Safety latch follows every foot of the lift, guaranteeing absolute safety.

PRICE \$125.00

For full particulars, apply to

Perkins Pump and Engine Co.

1023 N. Los Angeles St., Los Angeles

DR. W. F. DRAKE, E.M.

Mines and Mining

Reports and Examines Mines. Years of practical experience. Correspondence solicited

P. O. BOX 380

SONORA, Tuolumne County, Cal.


SIMONDS & WAINWRIGHT,



Chemical and Mining Engineers and Analysts

Working tests of Ores by all Processes. Experimental Work on Chemical and Metallurgical Processes. Instructions in Assaying and Chemistry.

No. 20 Platt Street New York



FOR conveying Ore, Coal, Slag and Matte. Send full particulars of your wants in writing for prices.

Robins Conveying Belt Co.,

147-149 Cedar Street, NEW YORK

JOHN T. REED

Assayer and Analytical Chemist

Assays made for all valuable metals. Analysis made of all valuable minerals. Special attention given to the sampling of mines. Estimating the value of and testing the nature of their ores. 100 pound lots of ore sampled, and working tests made by Cyanide, Amalgamation and Chlorination Processes.

OFFICE 622 COURT STREET,

San Bernardino, California

E. E. BURLINGAME'S

ASSAY OFFICE

Chemical

Laboratory

Established in Colorado, 1866. Samples by mail or express will receive prompt and careful attention. Gold and Silver Bullion refined, melted and assayed, or purchased.

Address 1736 and 1738 Lawrence St., Denver, Col.



The Bartlett Concentrating Table

Capacity 10 to 30 tons daily; size 4x8 feet; weight 800 lbs. Clean separation of all minerals without sizing. Price \$250. Send for description.

American Zinc Lead Co.,

CANON CITY, COLO.

Buyers of

ALL CLASSES OF

BULLION MATTE,
ORE and MILL
PRODUCTS
GOLD and SILVER
BARS

CONSOLIDATED

Kansas City Smelting AND Refining

COMPANY

SMELTING WORKS
LEADVILLE, COLO.; EL PASO, TEXAS;
ARGENTINE, KAN.; BOQUILLAS, MEX.

REFINERY:
ARGENTINE, KANSAS;

OUR PURCHASING AGENCIES:
C. D. Porter, Spokane, Wash.; J. H. Weddle, Denver
J. R. Jackson, Salt Lake City, Utah; H. R. Simpson,
El Paso Texas; C. E. Finney, Argentine, Kansas.

Manufacturers of

Alchemist-Brand
Blue Vitrol

Zinc Sulphates

THE PUEBLO Smelting and Refining Company,

PUEBLO, COLORADO.

BUYERS OF

Gold, Silver, Lead and Copper Ores,
Copper Matte and Bullion.

Refiners of Gold, Silver, Lead and Copper.

Manufacturers of Bar and Pig Lead, Lead Pipe, Antimonial Lead, Copper Ingots,
Granulated Test Leads and Litharge.

Pays Highest Prices for all classes of Ores.

Especial Attention to Sampling by most Approved Processes.

Quick Returns on all Consignments.



CHAS. B. BOOTHE & CO.

MINING AND MILLING MACHINERY AND SUPPLIES,

Hoists, Horse Whims, Buckets, Wire Rope, Ore Cars

129 SOUTH LOS ANGELES STREET,

LOS ANGELES, CAL

FRANK H. HOWE,

MECHANICAL ENGINEER

Boilers, Engines, Pumps, Complete Steam and Oil Running Plants

Mill and Mining Machinery

203 North Main Street, Los Angeles, Cal.

TELEPHONE MAIN 1357

RISDON IRON WORKS,

SAN FRANCISCO, CALIFORNIA

Cable Risdon's, Code—A. B. C. & Leibers

MANUFACTURERS OF

GOLD DREDGING MACHINERY AND COMPLETE EQUIPMENT for Placer Mines, OUR SPECIALTY.

We build Gold Dredges Complete in Running Order to handle 2,500 cubic yards per day at a cost of 3 cents per cubic yard.

We excavate 50 feet below water, 20 feet above water and handle boulders up to one ton weight. Send for Dredging Catalogues Nos. 15 and 16.

We also build all kinds of Mining, Milling Concentrating, Pumping, Air Compressing, Hydraulic, Water Wheel and Hoisting Machinery.

EVANS' HYDRAULIC GRAVEL ELEVATORS.

We publish 16 Catalogues. Write for one in the line you are interested in.



The Mining & Metallurgical Journal



Has its Offices | STIMSON BLOCK, LOS ANGELES, CAL., and
64-65 MERCHANTS' EXCHANGE, SAN FRANCISCO, CAL.

Write for Advertising Rates

Do you Want **MINING AND MILLING MACHINERY** and do you want **QUICKLY** to get it

If You Do, Address


Fraser & Chalmers, 133 FULTON STREET, CHICAGO

whose works are exclusively devoted to and adapted for the manufacture of Mining and Ore Reducing Machinery.

During the month of January, 1898, Fraser and Chalmers' Chicago Works received orders for Mills amounting to a total of

Eight Hundred and Fifteen [815] Stamps

and it is significant of their resources that even with this great amount of work in hand, they are still in position to contract for additional work for which **QUICK SHIPMENT** can be made.



JOSHUA HENDY MACHINE WORKS, Nos. 38 to 44 Fremont St. SAN FRANCISCO, CAL.


Manufacturers of and Dealers in

The Latest Improved

Quartz Milling, Pumping, Hoisting and Smelting Plants, Air Compressors and Rock Drills.

"HENDY" IMPROVED "TRIPLE-DISCHARGE" TWO-STAMP QUARTZ MILLS Boilers, Engines & Pumps of all capacities

PLANS, SPECIFICATIONS and ESTIMATES of COST SUBMITTED and CONTRACTS ENTERED INTO FOR FURNISHING and ERECTING MINING and MILLING PLANTS for all conditions of Use.



DOUBLE CYLINDER HOISTING ENGINE

BAKER IRON WORKS LOS ANGELES, CALIFORNIA

Manufacturers of

Mining and Milling Machinery, Atlas Engines and Boilers, Worthington Steam Pumps

Water Works Machinery A SPECIALTY

MINING ENGINES
Double AND Single Drum



— ALSO —

Hoisting Engines and Electric Hoists for Every Known use

LAMBERT HOISTING ENGINE CO.

SEND FOR OUR NEW CATALOGUE R

125 POINIER STREET, NEWARK, N. J.



Mining Timbers and Construction Lumber

(California Long Leaf Yellow Pine Lumber)

Prices given for delivery to any point in Mexico by Rail through Porfirio Diaz, Nuevo Laredo or Paso del Norte, and by Vessel through Gulf Ports of Tampico and Vera Cruz.

Bradley-Ramsay Lumber Co.

LOUISIANA, U. S. A.

ADDRESS INQUIRIES FOR PRICES TO

R. N. WATSON, AGENT.

APARTADO NO. 118 MONTERREY, N. L. MEXICO

PARKE & LACY COMPANY

21 and 23 Fremont St., San Francisco, Cal.



MINING MACHINERY

SOLE AGENTS FOR THE INGERSOLL-SERGEANT AIR COMPRESSORS AND ROCK DRILLS.

SOLE LICENSEE FOR THE MANUFACTURE AND SALE OF

THE ROPP STRAIGHT LINE FURNACE, For Roasting, Chlorinating and Desulphurizing Ores.

WE CARRY IN STOCK

Horizontal, Vertical and Portable Engines and Boilers. Rock Breakers, Cornish Rolls, Pulverizers, Concentrators, Ore Feeders. Hoisting Engines, Horse Power Hoisting Whims, Water Wheels, Steam Pumps, Ore Cars, Wire Rope, Ore Buckets, Water Buckets, Skips. Blowers and Exhaust Fans, Shafting and Pulleys, Belting, Oils and Mine Supplies. **Manganese Steel Shoes and Dies**

Estimates furnished for complete plants for hoisting, crushing, smelting, concentrating and stamp mills.

